



To: Members of Dublin City Council

From: Marsha I. Grigsby, City Manager 

Date: June 27, 2014

Initiated By: Terry D. Foegler, Director of Strategic Initiatives/Special Projects
Philip K. Hartmann, Assistant Law Director

Re: **Amended Ordinance 61-14 – Dale Drive Properties, LLC**
Ordinance 62-14 – G&I VI Sycamore Ridge, LLC
Ordinance 63-14 – Store Master Funding IV, LLC
(Related to North/South Connector between Tuller Ridge and Dale Drives)

Background

As Council is aware, the City has been engaged in the planning and design of several important public infrastructure improvement projects for the Bridge Street Corridor. These projects have received increased attention in recent months with the Bridge Street River Corridor urban design framework planning effort. These efforts further refined the planning for the riverfront parkland and right of way and other related public improvement projects in the area.

This project is for the construction of a north to south connection between the existing Tuller Ridge and Dale Drives (the "Project"). The properties subject to the "Ordinances to Appropriate" constitute the beginning of the construction of the grid format right of way system planned for the Corridor. The City must obtain property interests from three landowners located within the City in order to construct this Project.

- The first property owner is Dale Drive Properties, LLC ("Dale Drive"). Dale Drive owns property located adjacent to and east of the current Dale Drive. The City must obtain a 1.49 acre fee simple interest, a 0.384 acre fee simple interest, and a 0.366 acre slope easement. Additionally, the City must obtain the entire southern portion of the property in fee simple consisting of 0.815 acre for the relocation of Central Ohio Transit Authority Park and Ride.
- The second property owner is G&I VI Sycamore Ridge, LLC ("Sycamore Ridge"). Sycamore Ridge owns property located adjacent to and south of the current Tuller Ridge Drive. The City must obtain a 0.385 acre fee simple interest, a 0.004 acre fee simple interest, and a 0.320 acre temporary easement.
- The third property owner is Store Master Funding IV, LLC ("Store Master"). Store Master owns the third property in which the City must obtain a 0.013 acres fee simple interest and a 0.020 acre temporary easement.

The City is hopeful that an amicable resolution may be reached with the property owners; however, this Ordinance authorizes the law director's office to initiate the eminent domain process in the event that negotiations are unsuccessful.

The City is requesting emergency action on July 1 for the immediate preservation of the public peace, health, safety, or welfare, and for the further reason that obtaining the property interest is necessary for the advancement of this Project.

Acquisition

The City will be acquiring only the property interest necessary for the construction of the Project from the three property owners. The City had the property interests appraised; the appraised values are detailed below.

Dale Drive Ord. 61-14 (273-008242)

Property Interest Acquiring	Description	Appraisal Value
Fee Simple Interest	1.490 acre ±	\$268,200.00
Fee Simple Interest	0.384 acre ±	\$69,120.00
Fee Simple Interest	<i>0.815 acre ±</i>	<i>\$146,700.00</i>
Slope Easement	0.366 acre ±	\$52,704.00
Total		\$536,724.00

Sycamore Ridge Ord. 62-14 (273-009150)

Property Interest Acquiring	Description	Appraisal Value
Fee Simple Interest	0.385 acre ±	\$69,300.00
Fee Simple Interest	0.004 acre ±	\$720.00
Temporary Easement	0.320 acre ±	\$5,760.00
Site Improvements	Trees, Stone, Lawn, etc.	\$5,800.00
Total		\$81,580.00

Store Master Ord. 63-14 (273-011148)

Property Interest Acquiring	Description	Appraisal Value
Fee Simple Interest	0.013 acre ±	\$2,340.00
Temporary Easement	0.020 acre ±	\$360.00
Total		\$2,700.00

Recommendation

Staff recommends approval of Ordinances 61-14 (Amended), 62-14, and 63-14 by emergency at the second reading/public hearing on July 1, 2014 as the construction of the Project is necessary for public welfare and safety, and approval of the Ordinances will keep the Project moving forward.

RECORD OF ORDINANCES

Ordinance No. **61-14 (Amended)**

Passed _____, 20____

AN ORDINANCE AUTHORIZING THE APPROPRIATION OF A 1.490 ACRE, MORE OR LESS, FEE SIMPLE INTEREST; A 0.845 ACRE, MORE OR LESS, FEE SIMPLE INTEREST; A 0.384 ACRE, MORE OR LESS, FEE SIMPLE INTEREST AND A 0.366 ACRE, MORE OR LESS, SLOPE EASEMENT, FROM PROPERTY LOCATED ADJACENT TO AND NORTHEAST OF DALE DRIVE OWNED BY DALE DRIVE PROPERTIES, LLC, TO CONNECT DALE AND TULLER RIDGE DRIVES AND FOR THE CONSTRUCTION OF THE NEW PARK AVENUE, AND DECLARING AN EMERGENCY.

WHEREAS, the City of Dublin (the "City") is preparing to extend Dale Drive to the north to connect with Tuller Road (the "Project"); and

WHEREAS, the Project requires that the City obtain three fee simple interests and a slope easement from Dale Drive Properties, LLC (FKA "Dale Holding Co. of Columbus, LLC,") as described in the Exhibits labeled "A" and depicted in the Exhibits labeled "B," all attached hereto, said property interest located in the City of Dublin, County of Franklin, State of Ohio.

NOW, THEREFORE, BE IT ORDAINED by the Council of the City of Dublin, State of Ohio, _____ of the elected members concurring that:

Section 1. Council considers it necessary and declares its authorization to appropriate for the appraised value of Five Hundred Thirty Six Thousand Seven Hundred Twenty-Four Dollars (\$536,724.00), for the purpose of extending and connecting Dale and Tuller Ridge Drives, three fee simple interests and a slope easement as described in the Exhibits labeled "A" and depicted in the Exhibits labeled "B," all attached hereto.

Section 2. The City Law Director's office is hereby authorized to file a petition for appropriation in the county Court of Common Pleas should it become necessary.

Section 3. This Ordinance is declared to be an emergency necessary for the immediate preservation of the public peace, health, safety or welfare, and for the further reason that obtaining the property interest is necessary for the advancement of this Project. The Ordinance shall therefore take effect immediately upon passage.


Passed this _____ day of _____, 2014.

Mayor – Presiding Officer

ATTEST:

Clerk of Council

\ICM\DATA\01\Project\0120130451\Drawings\Overall Exhibits\Property Acquisition Exhibits\2014-08-03 Property Exhibit-MColor.dwg Last Saved By: dvanice, 6/27/2014 12:51 PM Last
 Printed By: Vance, David, 4/1/2014 2:06 PM
 4 Xrefs: 20121872-CS-REFR-PHOT, 79607650, 79857650, 20121872-CP-ROAD-REFR-N




2013 Aerial Photo

NOTE:
Property lines are based on Franklin County Auditor's GIS Information.

-  Sycamore Ridge Site Boundary
PID: (273-009150 & 273-009096)
-  Store Master Funding Site Boundary
PID: (273-011148)
-  Dale Drive Properties LLC Site Boundary
PID: (273-008242)

-  Proposed Right-of-Way
-  Slope Easement
-  Public Greenway
-  Temporary Easement
-  Relocated COTA Park & Ride Site




 CITY OF DUBLIN
**DALE DRIVE - TULLER
 RIDGE DRIVE
 CONNECTOR
 RIGHT OF WAY EXHIBIT**


 Evans, McWhorter, Hamblen & Tillon, Inc.
 Engineers • Surveyors • Planners • Scientists
 6500 New Albany Road, Columbus, OH 43054
 Phone: 614.775.4500 Fax: 614.775.3648
 emht.com

June 27, 2014
 1" = 100'
 20130451
 1 of 1

1.490 ACRE

Situated in the State of Ohio, County of Franklin, City of Dublin, lying in Quarter Township 3, Township 2, Range 19, United States Military Lands, and being part of that 6.202 acre tract conveyed to Dale Holding Co. of Columbus, LLC by deed of record in Instrument Number 200504120068206 (all references are to the records of the Recorder's Office, Franklin County, Ohio) and being more particularly described as follows:

Beginning for reference, at a 5/8 inch rebar found in a monument box at the centerline intersection of State Route 161 (right-of-way width varies) with Dale Drive (60 foot right-of-way width) as dedicated in Plat Book 58, Pages 81 and 82;

thence with the centerline of said Dale Drive, the following courses and distances:

North 02°31'25" East, a distance of 518.36 feet to a point of curvature;

with a curve to the left, having a central angle of 51°18'55", a radius of 400.00 feet, an arc length of 358.25 feet, and a chord that bears North 23°08'03" West, a chord distance of 346.39 feet to a point;

thence North 41°12'30" East, across said Dale Drive, a distance of 30.00 feet to an iron pin set at a corner common to said 6.202 acre tract and that 1.635 acre tract conveyed to Store Master Funding IV, LLC by deed of record in Instrument Number 201307020111012, in the easterly right-of-way line of said Dale Drive, being the TRUE POINT OF BEGINNING;

thence with the easterly right-of-way line of said Dale Drive and with the westerly line of said 6.202 acre tract, with a curve to the left, having a central angle of 18°22'25", a radius of 430.00 feet, an arc length of 137.89 feet and a chord that bears North 57°58'43" West, a chord distance of 137.30 feet to a 3/4 inch iron pipe found capped R.D. Zande at a corner common to said 6.202 acre tract and that 1.200 acre tract conveyed to Central Ohio Transit Authority by deed of record in Official Record 29294B09;

thence North 03°35'40" East, with the line common to said 6.202 acre tract and said 1.200 acre tract, a distance of 223.86 feet to a 3/4 inch iron pipe found capped R.D. Zande at a corner common to said 6.202 acre tract and said 1.200 acre tract, in the southerly line of that 15.097 acre tract conveyed to Scioto Tuller Acquisition, LLC by deed of record in Instrument Number 201308160140286;

thence South 86°21'53" East, with the northerly line of said 6.202 acre tract, with the southerly line of said 15.097 acre tract, with the southerly line of that 0.821 acre tract conveyed to The City of Dublin, Ohio by deed of record in Instrument Number 201212310201439 and with the southerly line of that 15.459 acre tract conveyed as Parcel I to G&I VI Sycamore Ridge LLC by deed of record in Instrument Number 200803100036370, (passing a 3/4 inch iron pipe found capped R.D. Zande at a distance of 59.41 feet) a total distance of 66.34 feet to an iron pin set;

thence across said 6.202 acre tract, the following courses and distances:

South 05°44'51" East, a distance of 30.41 feet to an iron pin set;

South 86°21'53" East, a distance of 555.94 feet to an iron pin set in the easterly line of said 6.202 acre tract and in the westerly line of that 5.270 acre tract conveyed to Wendy's International, Inc., by deed of record in Deed Book 3596, Page 274;

thence South 02°31'25" West, with the easterly line of said 6.202 acre tract and with the westerly line of said 5.270 acre tract, a distance of 76.01 feet to an iron pin set;

thence across said 6.202 acre tract, the following courses and distances:

North 86°21'53" West, a distance of 544.86 feet to an iron pin set;

South 05°44'51" East, a distance of 26.93 feet to an iron pin set at a point of curvature;

with said curve to the left, having a central angle of 19°37'49", a radius of 470.00 feet, an arc length of 161.03 feet and a chord that bears South 15°33'46" East, a chord distance of 160.24 feet to an iron pin set in a line common to said 6.202 acre tract and said 1.635 acre tract;

thence South 78°57'25" West, with said common line, a distance of 20.65 feet to the TRUE POINT OF BEGINNING and containing 1.490 acres, more or less.

1.490 ACRE

-2-

Subject, however, to all legal rights-of-way and/or easements, if any, of previous record.

Iron pins set, where indicated, are iron pipes, thirteen sixteenths (13/16) inch inside diameter, thirty (30) inches long with a plastic plug placed in the top bearing the initials EMHT INC.

The Bearings shown hereon are based on the Ohio State Plane Coordinate System South Zone as per NAD83 (1986 Adjustment). Control for bearings was from coordinates of monuments FRANK 73 and FRANK 74, having a bearing of South 73° 57' 18" East, established by the Franklin County Engineering Department, using Global Positioning System procedures and equipment.

This description is based on an actual field survey performed by or under the direct supervision of Joshua M. Meyer, Registered Surveyor Number 8485 in April 2013.

EVANS, MECHWART, HAMBLETON & TILTON, INC.

Joshua M. Meyer
Professional Surveyor No. 8485

Date

JMM
1_490 ac 20140589-VS-BNDY-02

0.384 ACRE

Situated in the State of Ohio, County of Franklin, City of Dublin, lying in Quarter Township 3, Township 2, Range 19, United States Military Lands, and being part of that 6.202 acre tract conveyed to Dale Holding Co. of Columbus, LLC by deed of record in Instrument Number 200504120068206 (all references are to the records of the Recorder's Office, Franklin County, Ohio) and being more particularly described as follows:

Beginning for reference, at a 5/8 inch rebar found in a monument box at the centerline intersection of State Route 161 (right-of-way width varies) with Dale Drive (60 foot right-of-way width) as dedicated in Plat Book 58, Pages 81 and 82;

thence with the centerline of said Dale Drive, the following courses and distances:

North 02°31'25" East, a distance of 518.36 feet to a point of curvature;

with a curve to the left, having a central angle of 51°18'55", a radius of 400.00 feet, an arc length of 358.25 feet, and a chord that bears North 23°08'03" West, a chord distance of 346.39 feet to a point;

thence North 41°12'30" East, across said Dale Drive, a distance of 30.00 feet to an iron pin set at a corner common to said 6.202 acre tract and that 1.635 acre tract conveyed to Store Master Funding IV, LLC by deed of record in Instrument Number 201307020111012, in the easterly right-of-way line of said Dale Drive;

thence with the easterly right-of-way line of said Dale Drive and with the westerly line of said 6.202 acre tract, with a curve to the left, having a central angle of 18°22'25", a radius of 430.00 feet, an arc length of 137.89 feet and a chord that bears North 57°58'43" West, a chord distance of 137.30 feet to a 3/4 inch iron pipe found capped R.D. Zande at a corner common to said 6.202 acre tract and that 1.200 acre tract conveyed to Central Ohio Transit Authority by deed of record in Official Record 29294B09;

thence North 03°35'40" East, with the line common to said 6.202 acre tract and said 1.200 acre tract, a distance of 223.86 feet to a 3/4 inch iron pipe found capped R.D. Zande at a corner common to said 6.202 acre tract and said 1.200 acre tract, in the southerly line of that 15.097 acre tract conveyed to Scioto Tuller Acquisition, LLC by deed of record in Instrument Number 201308160140286;

thence South 86°21'53" East, with the northerly line of said 6.202 acre tract, with the southerly line of said 15.097 acre tract, with the southerly line of that 0.821 acre tract conveyed to The City of Dublin, Ohio by deed of record in Instrument Number 201212310201439 and with the southerly line of that 15.459 acre tract conveyed as Parcel I to G&I VI Sycamore Ridge LLC by deed of record in Instrument Number 200803100036370, (passing a 3/4 inch iron pipe found capped R.D. Zande at a distance of 59.41 feet) a total distance of 66.34 feet to an iron pin set, being the TRUE POINT OF BEGINNING;

thence South 86°21'53" East, with the line common to said 6.202 acre tract and said 15.459 acre tract a distance of 560.32 feet, to the northeasterly corner of said 6.202 acre tract and the northwesterly corner of that 5.270 acre tract conveyed to Wendy's International, Inc., by deed of record in Deed Book 3596, Page 274 (reference a 3/4 inch iron pipe found 0.40 feet north and 0.16 feet east);

thence South 02°31'25" West, with the easterly line of said 6.202 acre tract and with the westerly line of 5.270 acre tract, a distance of 30.01 feet to an iron pin set

thence across said 6.202 acre tract, the following courses and distances:

North 86°21'53" West, a distance of 555.94 feet to an iron pin set;

0.384 ACRE

-2-

North 05°44'51" West, a distance of 30.41 feet to the TRUE POINT OF BEGINNING and containing 0.384 acre, more or less.

Subject, however, to all legal rights-of-way and/or easements, if any, of previous record.

Iron pins set, where indicated, are iron pipes, thirteen sixteenths (13/16) inch inside diameter, thirty (30) inches long with a plastic plug placed in the top bearing the initials EMHT INC.

The Bearings shown hereon are based on the Ohio State Plane Coordinate System South Zone as per NAD83 (1986 Adjustment). Control for bearings was from coordinates of monuments FRANK 73 and FRANK 74, having a bearing of South 73° 57' 18" East, established by the Franklin County Engineering Department, using Global Positioning System procedures and equipment.

This description is based on an actual field survey performed by or under the direct supervision of Joshua M. Meyer, Registered Surveyor Number 8485 in April 2013.

EVANS, MECHWART, HAMBLETON & TILTON, INC.

Joshua M. Meyer
Professional Surveyor No. 8485

Date

**SLOPE EASEMENT
0.366 ACRE**

Situated in the State of Ohio, County of Franklin, City of Dublin, located in Quarter Township 3, Township 2, Range 19, United States Military Lands, being across that 6.202 acre tract conveyed to Dale Holding Co. of Columbus, LLC by deed of record in Instrument Number 200504120068206 (all references refer to the records of the Recorder's Office, Franklin County, Ohio), and being described as follows:

Beginning, for reference, at a southwesterly corner of said 6.202 acre tract, a northwesterly corner of that 1.635 acre tract conveyed to Store Master Funding IV, LLC by deed of record in Instrument Number 201307020111012, being the easterly right-of-way line of Dale Drive (60 foot right-of-way width) of record in Plat Book 58, Pages 81 and 82;

thence North $78^{\circ} 57' 25''$ East, with the southerly line of said 6.202 acre tract, a distance of 20.65 feet a point on the arc of a curve to the right, being the TRUE POINT OF BEGINNING;

thence across said 6.202 acre tract, the following courses and distances:

with the arc of said curve to the right, having a central angle of $19^{\circ} 37' 49''$, a radius of 470.00 feet, an arc length of 161.03 feet, a chord bearing and distance of North $15^{\circ} 33' 46''$ West, 160.24 feet to a point;

North $05^{\circ} 44' 51''$ West, a distance of 26.93 feet to a point; and

South $86^{\circ} 21' 53''$ East, a distance of 544.86 feet to a point in the westerly line of that 5.270 acre tract conveyed to Wendy's International, Inc., by deed of record in Deed Book 3596, Page 274;

thence South $02^{\circ} 31' 25''$ West, with said westerly line, a distance of 14.23 feet to a point;

thence across said 6.202 acre tract, the following courses and distances:

North $86^{\circ} 41' 25''$ West, a distance of 235.08 feet to a point;

South $86^{\circ} 33' 36''$ West, a distance of 201.80 feet to a point;

North $85^{\circ} 04' 47''$ West, a distance of 76.06 feet to a point;

South $02^{\circ} 27' 58''$ East, a distance of 78.94 feet to a point; and

South $24^{\circ} 57' 43''$ East, a distance of 64.39 feet to a point in the northerly line of said 1.635 acre tract;

thence South $78^{\circ} 57' 25''$ West, with said northerly line, a distance of 16.41 feet to the TRUE POINT OF BEGINNING, and containing 0.366 acre of land, more or less.

EVANS, MECHWART, HAMBLETON & TILTON, INC.

Joshua M. Meyer
Registered Surveyor No. 8485

1.876 ACRE

Situated in the State of Ohio, County of Franklin, City of Dublin, lying in Quarter Township 3, Township 2, Range 19, United States Military Lands, and being part of that 6.202 acre tract conveyed to Dale Holding Co. of Columbus, LLC by deed of record in Instrument Number 200504120068206 (all references are to the records of the Recorder's Office, Franklin County, Ohio) and being more particularly described as follows:

Beginning for reference, at a 5/8 inch rebar found in a monument box at the centerline intersection of State Route 161 (right-of-way width varies) with Dale Drive (60 foot right-of-way width) as dedicated in Plat Book 58, Pages 81 and 82;

thence with the centerline of said Dale Drive, the following courses and distances:

North 02°31'25" East, a distance of 518.36 feet to a point of curvature;

with a curve to the left, having a central angle of 51°18'55", a radius of 400.00 feet, an arc length of 358.25 feet, and a chord that bears North 23°08'03" West, a chord distance of 346.39 feet to a point;

thence North 41°12'30" East, across said Dale Drive, a distance of 30.00 feet to an iron pin set at a corner common to said 6.202 acre tract and that 1.635 acre tract conveyed to Store Master Funding IV, LLC by deed of record in Instrument Number 201307020111012, in the easterly right-of-way line of said Dale Drive;

thence North 78°57'25" East, with a line common to said 6.202 acre tract and said 1.635 acre tract, a distance of 20.65 feet to an iron pin set, being the TRUE POINT OF BEGINNING;

thence across said 6.202 acre tract, the following courses and distances:

with a curve to the right, having a central angle of 19°37'49", a radius of 470.00 feet, an arc length of 161.03 feet, and a chord that bears North 15°33'46" West, a chord distance of 160.24 feet, to an iron pin set at a point of tangency;

North 05°44'51" West, a distance of 26.93 feet to an iron pin set;

South 86°21'53" East, a distance of 544.86 feet to an iron pin set in the easterly line of said 6.202 acre tract and in the westerly line of that 5.270 acre tract conveyed to Wendy's International, Inc., by deed of record in Deed Book 3596, Page 274;

thence South 02°31'25" West, with the easterly line of said 6.202 acre tract and with the westerly line of said 5.270 acre tract, a distance of 150.00 feet to an iron pin set at a common corner of said 6.202 acre tract and said 1.635 acre tract;

thence with the lines common to said 6.202 acre tract and said 1.635 acre tract, the following courses and distances:

North 86°52'35" West, a distance of 397.63 feet to an iron pin set;

thence South 78°57'25" West, a distance of 96.22 feet to the TRUE POINT OF BEGINNING and containing 1.876 acres, more or less.

Subject, however, to all legal rights-of-way and/or easements, if any, of previous record.

Iron pins set, where indicated, are iron pipes, thirteen sixteenths (13/16) inch inside diameter, thirty (30) inches long with a plastic plug placed in the top bearing the initials EMHT INC.

The Bearings shown hereon are based on the Ohio State Plane Coordinate System South Zone as per NAD83 (1986 Adjustment). Control for bearings was from coordinates of

1.876 ACRE

-2-

monuments FRANK 73 and FRANK 74, having a bearing of South 73° 57' 18" East, established by the Franklin County Engineering Department, using Global Positioning System procedures and equipment.

This description is based on an actual field survey performed by or under the direct supervision of Joshua M. Meyer, Registered Surveyor Number 8485 in April 2013.

EVANS, MECHWART, HAMBLETON & TILTON, INC.

Joshua M. Meyer
Professional Surveyor No. 8485

Date


JMM
1_876 ac 20140589-VS-BNDY-02

SURVEY OF ACREAGE PARCELS

QUARTER TOWNSHIP 3, TOWNSHIP 2, RANGE 19

UNITED STATES MILITARY LANDS

CITY OF DUBLIN, COUNTY OF FRANKLIN, STATE OF OHIO




SURVEY NOTE:
 This survey was prepared using documents of record, prior plats of survey, and observed evidence located by an actual field survey.

BASIS OF BEARINGS:
 The bearings shown hereon are based on the Ohio State Plane Coordinate System South Zone as per NAD83 (1986 Adjustment). Control for bearings was from coordinates of monuments FRANK 73 and FRANK 74, having a bearing of South 73° 57' 18" East, established by the Franklin County Engineering Department, using Global Positioning System procedures and equipment.

By Joshua M. Meyer Date _____
 Professional Surveyor No. 8485

- = STONE FND.
- = MON. FND.
- = I.P. FND.
- = I.P. SET
- = MAG. NAIL SET
- = MAG. NAIL SET
- = R.R. SPK. FND.
- △ = R.R. SPK. SET
- = P.K. NAIL FND.
- I.P. Set are 1 3/16" I.D. iron pipe with cap inscribed EMHT INC



EMHT <small>Evans, Mechwart, Hambleton & Tiboni, Inc. Engineers • Surveyors • Planners • Scientists 5500 New Albany Road, Columbus, OH 43064 Phone: 614.273.4500 Toll Free: 888.775.3445 emht.com</small>		Date: April 7, 2014
		Scale: 1" = 60'
		Job No: 2014-0589
		Sheet: 1 of 1
REVISIONS		
MARK	DATE	DESCRIPTION

2/2014 11:52:28 AM 4/7/2014 11:52:28 AM

0.815 ACRE

Situated in the State of Ohio, County of Franklin, City of Dublin, lying in Lot 11, Quarter Township 3, Township 2, Range 19, United States Military Lands, and being part of that 4.567 acre tract conveyed to Dale Drive Properties LLC by deed of record in Instrument Number 201405020054216 (all references are to the records of the Recorder's Office, Franklin County, Ohio) and being more particularly described as follows:

Beginning for reference, at a 5/8 inch rebar found in a monument box at the intersection of the centerline of Survey, Construction and Right-of-way of State Route 161 (right-of-way width varies) as shown on Right-of-way Plan Set FRA-161-4.77 on file with the Ohio Department of Transportation, District 6, Delaware Ohio, with the centerline of Dale Drive (60 foot right-of-way width) as dedicated in Plat Book 58, Pages 81 and 82;

thence North 02° 31' 25" East, with the centerline of said Dale Drive, a distance of 518.36 feet to a point of curvature;

thence continuing with said centerline, with a curve to the left, having a central angle of 41° 46' 26", a radius of 400.00 feet, an arc length of 291.64 feet, and a chord that bears North 18° 21' 49" West, a chord distance of 285.22 feet to a point;

thence North 50° 44' 58" East, across said Dale Drive, a distance of 30.00 feet to an iron pin set at a corner common to said 4.567 acre tract and that 1.635 acre tract conveyed to Store Master Funding IV, LLC by deed of record in Instrument Number 201307020111012, in the easterly right-of-way line of said Dale Drive, being the TRUE POINT OF BEGINNING;

thence with a line common to said 4.567 acre tract and said 1.635 acre tract, the following courses and distances:

North 78° 57' 25" East, a distance of 70.48 feet to an iron pin set;

South 86° 52' 35" East, a distance of 180.80 feet to a 3/4 inch iron pipe found; and

South 02° 31' 25" West, a distance of 200.00 feet to an iron pin set on the northerly line of that 4.519 acre tract conveyed to Joseph Realty, LLC by deed of record in Instrument Number 201009290126830;

thence North 86° 52' 35" West, with the line common to said 4.567 and 4.519 acre tracts, a distance of 108.80 to a 3/4 inch iron pipe found in the easterly right-of-way line of said Dale Drive;

thence with said right-of-way line, the following courses and distances:

North 02° 31' 25" East, a distance of 60.00 feet to an iron pin set;

North 86° 52' 35" West, a distance of 63.25 feet to a 3/4 inch iron pipe capped "Bird & Bull" found;

with the arc of a curve to the left, having a central angle of 19° 30' 41", a radius of 430.00 feet, an arc length of 146.43 feet, a chord bearing of North 29° 29' 41" West and chord distance of 145.73 feet, to the TRUE POINT OF BEGINNING, containing 0.815 acre, more or less.

Subject, however, to all legal rights-of-way and/or easements, if any, of previous record.

Iron pins set, where indicated, are iron pipes, thirteen sixteenths (13/16) inch inside diameter, thirty (30) inches long with a plastic plug placed in the top bearing the initials EMHT INC.

The Bearings shown hereon are based on the Ohio State Plane Coordinate System South Zone as per NAD83 (1986 Adjustment). Control for bearings was from coordinates of

0.815 ACRE

-2-

monuments FRANK 73 and FRANK 74, having a bearing of South 73° 57' 18" East, established by the Franklin County Engineering Department, using Global Positioning System procedures and equipment.

This description is based on an actual field survey performed by or under the direct supervision of Joshua M. Meyer, Registered Surveyor Number 8485 in April 2013.



JMM:uk
0_815 ac 20140871-VS-BNDY-01.doc

EVANS, MECHWART, HAMBLETON & TILTON, INC.

Joshua M. Meyer
Professional Surveyor No. 8485

6-25-2014

Date




* PENDING DEED ORDER *

SURVEY OF ACREAGE PARCEL

LOT 11, QUARTER TOWNSHIP 3, TOWNSHIP 2, RANGE 19


UNITED STATES MILITARY LANDS

CITY OF DUBLIN, COUNTY OF FRANKLIN, STATE OF OHIO




SURVEY NOTE:
 This survey was prepared using documents of record, prior plats of survey, and observed evidence located by an actual field survey.

BASIS OF BEARINGS:
 The Bearings shown hereon are based on the Ohio State Plans Coordinate System South Zone as per NAD83 (1986 Adjustment). Control for bearings was from coordinates of monuments FRANK 73 and FRANK 74, having a bearing of South 73° 57' 18" East, established by the Franklin County Engineering Department, using Global Positioning System procedures and equipment.



By Josh M. Meyer 6-25-2014
 Professional Surveyor No. 8485 Date



EMHT Evers, Mechwart, Hamilton & Tilton, Inc. Engineers + Surveyors + Planners + Scientists 5500 New Albany Road, Columbus, OH 43054 Phone: 614.775.4500 Toll Free: 888.773.3648 emht.com		Date: June 25, 2014
		Scale: 1" = 60'
Job No: 2014-0871		Sheet: 1 of 1
REVISIONS		
MARK	DATE	DESCRIPTION