

## Addendum # 1 -- 15-012.0-CIP -- E-Mail Coversheet 2015 Crack Seal Program

<i>Planholder</i>	<i>Company E-Mail</i>	<i>Company Contact</i>
Aero-Mark, Inc.	aeromark@outlook.com	Mike Kreen
Aero-Mark, Inc.	tusharstuart@gmail.com	Charles Tushar
Allied Construction Industries	api@americanpavements.com	Candi Oakley
American Pavement Solutions	rburkel@ameripavement.com	Bob Burkel
American Pavements, Inc.	api@americanpavements.com	Brooke Taylor
AnnSeal, Inc.	rmartinez@annseal.com	Rocky Martinez
Builders Exchange	ametcalf@bxohio.com	Andrea Metcalf
C&C Asphalt Maintenance LLC	ccasphaltmaintenance@yahoo.com	Lance Cartwright
Columbus Asphalt Paving, Inc.	dpower@capasphalt.com	David Power
Construction Journal	ted.blaicher@constructionjournal.com	Ted Blaicher
Crafco, Inc	jeremiah.stratton@crafco.com	Jeremiah Stratton
Deltek		Imma Tabique
Duraseal	boblester@durasealohio.com	Bob Lester
Interstate Sealant and Concrete, Inc	sleppert@interstatesealant.com	Sean Leppert
ISQFT	jcoulter@isqft.com	Jenae Coulter
KPD, Ltd. LLC	kpdemers2@gmail.com	Ken DeMers
OPC Contracting, Inc.	mconley@opc-inc.com	Mason Conley
Scodeller Construction	matts@scodellerconstruction.com	Matt Sharkey

Please sign, date and return by e-mail to [hgeorge@dublin.oh.us](mailto:hgeorge@dublin.oh.us) to verify receipt of this addendum. Attach signed copy of addendum to bid package when submitting a bid.

Received by: \_\_\_\_\_ Date: \_\_\_\_\_



Date of Addendum  
**Feb 18, 2017**

**City of Dublin -- Division of Engineering**  
5800 Shier-Rings Road Dublin OH 43016  
Phone (614) 410-4640 Fax (614) 761-650

---

Addendum # 1 -- 15-012.0-CIP -- E-Mail Coversheet  
**2015 Crack Seal Program**

Strawser Paving Company, Inc.

Jordan Traylinek

---

WL Markers

jnott@wlmarkers.com

Jocab Nott

---

Wolverine Sealcoating LLC

sales@wolverineseal.com

Kit Wingle

---

Please sign, date and return by e-mail to [hgeorge@dublin.oh.us](mailto:hgeorge@dublin.oh.us) to verify receipt of this addendum. Attach signed copy of addendum to bid package when submitting a bid.

Received by: \_\_\_\_\_ Date: \_\_\_\_\_



Date of Addendum  
**Feb 18, 2017**

**City of Dublin -- Division of Engineering**  
5800 Shier-Rings Road Dublin OH 43016  
Phone (614) 410-4640 Fax (614) 761-650



# **SUPPLEMENTAL SPECIFICATIONS**

## **CONTRACT SPECIFICATIONS**

All contract specifications in this section are to be considered a part thereof. The specifications for this project shall be the The State of Ohio, Department of Transportation Construction and Material Specifications (ODOTCMS) 2013 edition.

## **OWNER**

All references to the "Owner" or the "City" shall identify The City of Dublin, Ohio.

## **CONSTRUCTION PERIOD**

The construction period for this project may begin on April 15, 2015 and shall end on the completion date June 30, 2015. The construction period includes an allocation for inclement weather. Any request for extension of the construction period due to inclement weather shall be presented to the engineer for consideration as soon as the contractor foresees the need for an extension to the construction period. This request should be supported by documentation showing the days lost due to the inclement weather. All work including all restoration shall be completed by the completion date.

## **SCHEDULE OF WORK**

A minimum 7 days advance notice of work is required prior of commencement of work.

## **SCHEDULE**

The Contractor shall submit a work schedule to the Engineer for review and approval at the time of the pre-construction meeting. This schedule will detail the timing of the work activities for the various sections of the project. The construction schedule shall be updated bi-monthly (twice each month), or whenever a substantial change in the schedule has occurred, and forwarded to the Engineer. A revised schedule shall be submitted with each request for payment. In the event that modifications to the schedule are necessary, the contractor shall provide the City with a minimum of 24 hours advance notice to scheduled work. The contractor shall provide the owner with a minimum of 24 hrs notice for all work.

## **MAINTENACE OF TRAFFIC, MOBILIZATION PUBLIC SAFETY & PUBLIC CONVENIENCE**

It is the intent of this contract that all items of street repair be scheduled and performed by the Contractor in a manner as to minimize inconvenience to pedestrian and vehicular traffic. It is also the intent to provide for and maintain access to residential, commercial, industrial and public properties to the maximum extent reasonable during the performance of the work. No street may be closed nor may any traffic movements be restricted without prior approval by the Engineer.

All traffic control devices shall be furnished, installed and maintained in accordance with the Ohio Manual of Uniform Traffic Control Devices current edition. The limits of the construction work shall be marked with the appropriate signage (Road Work, and End Road Work) prior to the commencement of any work or staging of equipment. Special Duty Police Officers having jurisdiction in the City of Dublin shall be substituted where reference is made to “flagger” for arterial streets.

By nature of the scope of this contract the contractor will need to mobilize to different areas at different times. The costs associated with such mobilization(s) shall be included with the unit costs of the work performed as a result of said mobilization.

An allowance for Law Enforcement Officer with Patrol Car has been provided for use on arterial streets. The contractor shall provide all other traffic control devices.

The costs for erection, maintenance and removal of all devices shall be included in the bid price for each item of work. Costs for special duty police officers shall be paid under Item 614 “LEO w/ Patrol Car”.

The Contractor shall provide adequate twenty-four (24) hour emergency telephone numbers to permit notification by the City in the event of a problem or emergency. Should notification be unable to be made or the Contractor fail to perform work of an immediate nature, the City will be reimbursed 2.5 times the cost to perform the work.

## **ENVIROMENTAL REGULATION**

The contractor shall be responsible for controlling dust, and containing debris resulting from saw cutting, excavation, pavement planning, demolition or other construction related activities. The contractor shall verify that all storm structures and piping are free of construction related debris following each phase of construction activity. The Engineer may request additional or other measures be taken by the contractor if the Engineer does not believe the contractors current method(s) are effective. The costs for complying with environmental regulations are to be included in the various unit costs associated with the construction project. This includes additional measures requested as noted above.

## **CONSTRUCTION NOISE**

Any devise shall not be operated at any time in such a manner that the noise created substantially exceeds the noise customarily and necessarily attendant to the reasonable and efficient performance of such equipment.

## **UTILITIES**

The Contractor shall notify the Ohio Utilities Protection Service (811) at least two (2) working days prior to performing any excavation. The contractor is responsible to utilize

care and to protect all utilities, public and private. The contractor is responsible to survey the existing conditions and mark the locations of visible irrigation system components. The contractor is to utilize care when working in areas that contain irrigation systems. Any damage to irrigation systems due to negligence on the part of the contractor shall be repaired at the expense of the contractor. Any damage to such utilities that the Engineer determines to be due to the contractor's neglect, shall be repaired at the expense of the contractor, without additional cost to the owner. Irrigation system repairs and repairs to underground dog fence shall be completed in a timely manner. Irrigation components in conflict with proposed work will be relocated (as directed by the Engineer) by the contractor under force account, or under other provisions made by the City. The Contractor is responsible for the support and protection of utilities in any excavation. The cost for this work is to be included in the price for each bid item.

## **COORDINATING WITH UTILITIES**

It is the Contractor's responsibility to coordinate their work with the private utilities as required. The utility owner may be required to brace, temporarily support, or relocate their respective utilities so that the proposed roadway work may proceed.

## **WORKING HOURS and RESTRICTIONS**

It is the intent of the City to keep inconvenience and disturbance to property owners to a minimum. The work day(s) shall be from 7 AM until 7 PM, Monday through Friday. If the Contractor desires to work on Saturdays or Holidays, or outside of these hours, the contractor should provide such request to the Engineer at least 48 hrs in advance. All work is to be scheduled to maintain the work area clean and safe and final restoration shall follow as soon as reasonably possible. Final Payment will not be made for any item until all work including cleanup and restoration associated with the item is completed. Equipment and materials shall not be stored in streets or rights of way without approval of the City.

## **EXISTING ROADWAY SECTION INFORMATION**

The listing of roadway segments is based on existing information. Roadway details are believed to be correct with respect to segment length, width and square yardage. Any difference shall be brought to the attention of the engineer within 24 hours of the contractor's determination that actual information is different than that provided.

## **GEOTECHNICAL INFORMATION**

No subsurface exploration of the project was performed.

## **INSPECTION**

All inspections shall be provided by the City of Dublin, unless otherwise provided herein.

## **COORDINATION**

The General Contractor is responsible for the scheduling and coordination of the work performed by their personnel as well as that of all subcontractors.

Contractor shall coordinate his work to facilitate work by others in the right-of-way and outside of the construction work limits.

## **PROPOSAL**

No extra compensation will be paid to the Contractor by reason of compliance with any of the requirements indicated in the Specifications, but payment shall be deemed to be included among the items, as bid upon, unless otherwise specifically provided.

## **CONSTRUCTION LAYOUT**

All construction limits, survey, elevation, and layout stakes for this roadway project shall be provided by the Contractor utilizing the included maps and street listing. The costs for such shall be included in the associated pay items unless specifically noted otherwise.

## **STAGING AREA**

The Contractor shall make their own provisions to provide staging area(s) if that area is outside the right-of-way. All areas disturbed shall be fully restored to their original conditions or better to the satisfaction of the City of Dublin. The contractor at his expense shall perform all restoration. Work close to existing trees shall require the installation of tree protection fencing.

## **REMOVAL OF CONSTRUCTION DEBRIS**

The Contractor shall remove construction debris on a daily basis. No construction materials are to be stored within any public R.O.W. The Contractor should be diligent in maintaining barricades to protect the work area. All excavated material and debris shall be immediately placed into truck or other vehicle for disposal. No trash shall be left on site or buried in excavations. Trash shall be immediately placed into proper receptacles or containers and disposed of by the contractor. Paving areas shall be swept clean of debris within 48 hours of completion of the paving operations.

## **STORAGE OF EQUIPMENT AND MATERIALS**

No materials, including pipe, shall be stored within twenty (20) feet of any intersecting street or driveway. During non-working hours, storage of equipment shall comply with these same requirements and shall not in any way relieve the Contractor of their legal responsibilities or

liabilities for the safety of the public. No material shall be stockpiled or dumped within the City Right-of-Way or on City owned property with out prior approval from the Engineer. All trailers or equipment parked in roadway shall be coned off for safety. Luminaries shall be utilized as requested.

## **CONSTRUCTION MATERIALS**

No alternates or deviations shall be permitted from those construction materials shown the plans. Bidders shall not submit alternates with their bid.

## **SURVEY MONUMENTATION**

The contractor shall carefully preserve survey reference points (e.g. bench marks, property corners, reference points, stakes and other survey reference monuments or markers). Where survey reference points are disturbed due to neglect or careless operations by the contractor, the contractor shall be responsible for resetting the survey reference points. Resetting of survey reference points shall be performed by an Ohio Professional Surveyor, licensed by the State of Ohio, as approved by the Engineer at the contractor's expense.