

## Addendum # 1 -- 15-031.0-CIP -- E-Mail Coversheet

### Boardwalk Improvement - S.R. 161 at Shawan Falls drive

<i>Planholder</i>	<i>Company E-Mail</i>	<i>Company Contact</i>
Allied Construction Industries	coakley@aci-construction.org	Candi Oakley
B K LAYER LLC	TYLERSTILLION@AOL.COM	Tyler Stillion
Builders Exchange	ametcalf@bxohio.com	Andrea Metcalf
Central Ohio Building Co. Inc.	wilbur@cobohio.com	Wilbur Ronk
ConstructConnect	ohio@isqft.com	Allen Blair
Construction Journal	donnad@thecj.com	Donna Dybzinski
Deltek	BidsInbound@deltek.com	John Smith
Enviro-Construction Co.	mcox64@earthlink.net	Mark Cox
Fifth Avenue Lumber Company	jmenzie@straitandlamp.com	Jacob Menzie
Johnson Cement LLC	rod@johnsoncement.com	Rod Johnson
Liberty Boardwalks	dyates@tlc-fab.com	Darryl Yates
McDaniels Construction Corp., Inc.	moncrief@mcdanielsconstruction.com	Dan Moncrief
North America Procurement Council In	lyra@napc.me	Lyra de Asis
Structural Erectors	jamesorr@structuralerectors.com	James Orr
The Blue Book Building & Construction	kstein@theblubook.com	Kathy Stein

Please sign, date and return by e-mail to [hgeorge@dublin.oh.us](mailto:hgeorge@dublin.oh.us) to verify receipt of this addendum. Attach signed copy of addendum to bid package when submitting a bid.

Received by: \_\_\_\_\_ Date: \_\_\_\_\_



Date of Addendum  
**Aug 26, 2016**

**City of Dublin -- Division of Engineering**  
5800 Shier-Rings Road Dublin OH 43016  
Phone (614) 410-4640 Fax (614) 761-650

**ADDENDUM NO. 1  
to the contract for**

**BOARDWALK IMPROVEMENTS  
S.R. 161 at SHAWAN FALLS  
15-031-CIP  
Bid Date: August 31, 2016**

**TO PROSPECTIVE BIDDERS:** The following changes shall be made part of the contract documents for this project:

**Request for Information:**

1. *What grade of plastic lumber do you require?* Answer: See revision to General Notes below. Composite lumber is now specified for the decking.

**COST ESTIMATE**

The cost estimate for the Project was \$85,000. The cost estimate has been revised to \$110,000.

**CONSTRUCION DRAWINGS**

**Add General Note:**

In the Invitation for Bids, it states that copies of the Contract documents are available to ODOT pre-qualified bidders. Remove reference for bidders to be ODOT pre-qualified. Bidders are not required to be ODOT pre-qualified.

General Notes – Sheet 6 of 9

Revise Note:

**FASTENERS**

PLASTIC LUMBER FASTENERS SHALL FOLLOW THE INSTALLATION REQUIREMENTS AS ESTABLISHED BY THE SUPPLIER.

TIMBER FASTENERS SHALL BE 2 ½" LONG #9 GALVANIZED STEEL SCREWS.

To Note:

**FASTENERS**

DOCKSIDER COMPOSITE DECKING BY TIMBERTECH SHALL BE USED FOR DECKING. FASTENERS/SCREWS SHALL FOLLOW THE INSTALLATION REQUIREMENTS AS ESTABLISHED BY THE SUPPLIER.

\* \* \* Beginning of Sheet 2 \* \* \*

SCREWS FOR THE COMPOSITE DECKING SHALL BE 3.0-INCHES LONG AND STAINLESS STEEL.

SCREWS FOR THE TIMBER MEMBERS SHALL BE 2.5-INCHES LONG #9 HOT-DIPPED GALVANIZED STEEL SCREWS OR APPROVED EQUAL.

Revise Note:

**TIMBER MEMBERS**

FURNISH AND INSTALL TIMBER MEMBERS AS SHOWN IN THE PLANS. TIMBER SHALL CONFORM TO AASHTO M 168 AND BE TREATED ACCORDING TO AASHTO M 133.

ALL LABOR, EQUIPMENT, AND MATERIALS NEEDED TO FURNISH AND INSTALL THE TIMBER MEMBERS AS SHOWN IN THESE PLANS SHALL BE INCLUDED IN THE RESPECTIVE TIMBER MEMBER ITEM.

To Note:

**TIMBER MEMBERS**

FURNISH AND INSTALL TIMBER MEMBERS AS SHOWN IN THE PLANS. TIMBER SHALL CONFORM TO THE 2016 ODOT 712.06 SPECIFICATION.

TIMBER MEMBERS SHALL BE SOUTHERN YELLOW PINE. SCREWS SHALL FOLLOW THE INSTALLATION REQUIREMENTS AS ESTABLISHED BY THE WOOD INDUSTRY.

PROVIDE WOOD MEMBERS THAT ARE SMOOTH AND SPLINTER FREE. WOOD SHALL BE S4S.

STAGGER BUTT ENDS OF THE RAIL TIMBER MEMBERS – SIMILAR TO EXISTING BOARDWALK RAILS – ON ALTERNATE POSTS. CENTER ALL BUTT END JOINTS ON THE POSTS.

Revise Note:

**2" X 6" PLASTIC LUMBER**

THE CONTRACTOR SHALL USE 2" X 6" PLASTIC LUMBER AS SUPPLIED BY:

PLASTIC LUMBER YARD  
220 E. WASHINGTON STREET  
NORRISTOWN, PA 19401  
(610) 227-3970  
[WWW.PLASTICLUMBERYARD.COM](http://WWW.PLASTICLUMBERYARD.COM)

THE CONTRACTOR MAY USE AN EQUIVALENT ALTERNATIVE SUPPLIER UPON APPROVAL BY THE ENGINEER.

THE PLASTIC LUMBER SHALL CLOSELY MATCH THE EXISTING TIMBER MEMBERS IN COLOR AND AS APPROVED BY THE ENGINEER.

\* \* \* End of Sheet 2 \* \* \*

\* \* \* Beginning of Sheet 3 \* \* \*

THE CONTRACTOR SHALL FOLLOW THE SPECIFICATIONS AND INSTALLATION REQUIREMENTS AS ESTABLISHED BY THE SUPPLIER.

ALL LABOR, EQUIPMENT, AND MATERIALS NEEDED TO FURNISH AND INSTALL THE 2" X 6" PLASTIC LUMBER AS SHOWN IN THESE PLANS SHALL BE INCLUDED IN ITEM – 2" X 6" PLASTIC LUMBER.

To Note:

**2" X 6" PLASTIC LUMBER**

THE CONTRACTOR SHALL USE 2" X 6" COMPOSITE LUMBER AS MANUFACTURED BY:

TIMBERTECH  
TYPE: DOCKSIDER – GREY IN COLOR  
1.25" X 5.5"

THE CONTRACTOR SHALL FOLLOW THE SPECIFICATIONS AND INSTALLATION REQUIREMENTS AS ESTABLISHED BY THE MANUFACTURER.

ALL LABOR, EQUIPMENT, AND MATERIALS NEEDED TO FURNISH AND INSTALL THE 2" X 6" COMPOSITE LUMBER AS SHOWN IN THESE PLANS SHALL BE INCLUDED IN ITEM – 2" X 6" PLASTIC LUMBER.

\* \* \* \* \*

**Addendum Approved By:**



Paul A. Hammersmith, PE                      8-29-2016  
Director of Engineering/City Engineer      Date

\* \* \* \* \*

**Terminus for Addendum No. 1  
Certification by Bidder**

Bidder shall sign and date one copy of this Addendum No. 1 and submit with his proposal as evidence of receipt and evaluation of same in his bid analysis.

**Signed:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Company:** \_\_\_\_\_