

**ADDENDUM NO. 1  
to the contract for  
Comprehensive Wayfinding System Phase 1A and 1B  
16-024.1-CIP  
Bid Date: February 7, 2017**

**TO PROSPECTIVE BIDDERS: The following changes shall be made part of the contract documents for this project:**

**INFORMATION**

1. A pre-bid meeting is not scheduled for this project. Please contact Tina Wawzkiewicz ([twawzkiewicz@dublin.oh.us](mailto:twawzkiewicz@dublin.oh.us)) with any questions regarding the bid package.
2. There are existing foundations for several of the proposed wayfinding signs. Where foundations are provided, the construction drawing plan sheets specify "Sign Foundation Provided by Others." See sheet 35, for example. The existing foundations have been prepared in coordination with the subject project. Sign assemblies have not been installed for sign types D1, D2, or D4.
3. Notes are also included on the construction drawing plan sheets to indicate if a sign assembly (sign support assembly, pedestal, base, and flat sheet sign) is to be delivered to the City for future installation by others. See sheet 35, for example. See sheets 4 and 4A for a list of sign assemblies to be delivered. Spare stock and flat sheet signs for future use are also to be delivered to the City, as detailed on sheets 4, 4A, and 80.
4. Quantities for Item 630, Signing, Misc.: Flat Sheet, Wayfinding Sign D1 (3'-11" x 6'-3 1/2") are calculated as follows:

44 initial panels for installation  
+ 4 initial panels for delivery to City, future installation by others  
+ 21 replacement panels for delivery to City, future installation by others  
= 69 Each

Spare sign panels are quantified separately. Other sign types follow the same method.

**BID SCHEDULE**

5. Please find a revised bid schedule attached and available for download. The quantity for reference line 29 has been updated.

**CONSTRUCTION DRAWINGS**

6. Please find revised construction drawing sheets 4, 5, and 9 attached. Quantities have been updated to more accurately reflect the plans.

\* \* \* Beginning of Sheet 2 \* \* \*

7. The overall size of sign type B2 is 4'-4 3/8" bottom width x 7'-0" height, including the frame. The overall size of the B2 sign panel, without the frame, is 4'-2 3/4" width x 6'-11 5/8" height. Please find revised construction drawing sheets, providing additional dimensions and details, on sheet 65 attached.

\* \* \* \* \*

Addendum Approved By:

Paul A. Hammersmith, PE                      01-27-2017  
Director of Engineering/City Engineer      Date

\* \* \* \* \*

**Terminus for Addendum No. 1  
Certification by Bidder**

Bidder shall sign and date one copy of this Addendum No. 1 and submit with his proposal as evidence of receipt and evaluation of same in his bid analysis.

**Signed:** \_\_\_\_\_ **Date:** \_\_\_\_\_

**Company:** \_\_\_\_\_