

Addendum # 1 -- 16-014.0-CIP -- E-Mail Coversheet Mid-Century Neighborhood Street Improvements

<i>Planholder</i>	<i>Company E-Mail</i>	<i>Company Contact</i>
Aero-Mark, Inc.	aeromark@outlook.com	Mike Krenn
Allied Construction Industries	coakley@aci-construction.org	Candi Oakley
Asplundh Construction Corp.	rjennings1@asplundh.com	Richard Jennings
Builders Exchange	ametcalf@bxohio.com	Andrea Metcalf
Cleary Construction, Inc.	estimating@clearyconst.com	Ryan Hunt
Columbus Asphalt Paving, Inc.	dpower@capasphalt.com	David Power
Complete General Construction Comp	estimators@cgclist.com	Whit Wardell
ConstructConnect	projects@isqft.com	Morgan Stinson
Construction Journal		Donna Dydbzinski
Construction Journal	p.exton@thecj.com	Pam Exton
Danbert Inc.	psutton@danbertinc.com	Phil Sutton
Darby Creek Excavating Inc.	amye.dce@gmail.com	AmyEsterbrook
Decker Construction Company		Jon Ewert
Deltek	dinadagdag@deltek.com	Dina Dagdag
E. C. Babbert	chanes@ecbabbert.com	Cecil Hanes
Elite Excavating Company of Ohio, Inc	dalestevens@eliteexcavating.com	Dale Stevens
Forterra Pipe	jon.laing@forterrabp.com	Jon Laing
George J. Igel & Company, Inc.	matt.check@igelco.com	Matt Check

Please sign, date and return by e-mail to hgeorge@dublin.oh.us to verify receipt of this addendum. Attach signed copy of addendum to bid package when submitting a bid.

Received by: _____ Date: _____



Date of Addendum
Feb 14, 2017

City of Dublin -- Division of Engineering
5800 Shier-Rings Road Dublin OH 43016
Phone (614) 410-4640 Fax (614) 761-650

Addendum # 1 -- 16-014.0-CIP -- E-Mail Coversheet

Mid-Century Neighborhood Street Improvements

GreenScapes Landscape Co.	tomkuhn@greenscapes.net	Thomas Kuhn
ISQFT	projects@isqft.com	Morgan Stinson
JD Striping & Services, Inc.	jdstriping@att.net	James Wimmer
Jess Howard	john.gordon@jesshoward.com	John Gordon
John Eramo & Sons, Inc.	jason@eramo.com	Jason Hazelbaker
Karvo Paving Company	karvo@karvocompanies.com	Donald Wortkoetter
McDaniels Construction Corp., Inc.	moncrief@mcdanielsconstruction.com	Dan Moncrief III
Peterman's Tree & Lawn Service	peterman_tree_srv@yahoo.com	James Peterman
Shelly & Sands, Inc.	bcolbert@shellyandsands.com	Betty Colbert
Shelly & Sands, Inc.	j.schultz@shellyandsands.com	Jeff Schultz
Strawser Paving Company, Inc.	clayS@strawserpaving.com	Clay Strawser
Sunesis Construction Co	astrunk@sunesiscc.com	Andrea Strunk
The Blue Book Building & Construction	kstein@mail.thebluebook.com	Kathy Stein
Trucco Construction Company	joel.cochran@truccoconstruction.com	Joel Cochran
US Utility Contractor Company, Inc.	dblend@usutilitycontractors.com	Dan Blend

Please sign, date and return by e-mail to hgeorge@dublin.oh.us to verify receipt of this addendum. Attach signed copy of addendum to bid package when submitting a bid.

Received by: _____ Date: _____



Date of Addendum
Feb 14, 2017

City of Dublin -- Division of Engineering
5800 Shier-Rings Road Dublin OH 43016
Phone (614) 410-4640 Fax (614) 761-650

**ADDENDUM NO. 1
to the contract for**

**Mid-Century Neighborhood Street Improvements
16-014-CIP**

Bid Opening Date: February 21, 2017

TO PROSPECTIVE BIDDERS: The following changes shall be made part of the contract documents for this project:

Bidding Requirements

Revise section 1.B.17.b to:

All bids shall remain open for acceptance for 90 days following the day of the Bid opening, but the City may, in its sole discretion, release any Bid and return the Bid Guaranty before that date.

Bid Items

Change:	Item 201	Tree Removed, 18" Size	28 EA
To:	Item 201	Tree Removed, 18" Size	29 EA
		(The removal of an additional 24" tree at 59 Grandview Drive)	
Add:	Item 661	Deciduous Shrub, 36", Taxus x media 'Densiformis'	3 EA
		(The installation of screening as directed at 250 Franklin Street)	
Add:	Item Special	Invisible Dog Fence Restored	1 LS

Proposal Notes

Add the following note:

Item Special – Invisible Dog Fence Restored

The contractor shall restore the existing invisible dog fence at 38 Marion Street. The original wire is located inside of the existing drive pipe. A new 2" conduit is included with the project for the purpose of installing a new wire under the drive.

Payment shall be made at the lump sum bid for Item Special - Invisible Dog Fence Restored and shall include all labor, equipment and materials necessary to perform the work noted above.

*** Beginning of Sheet 2 ***

Bid Tabs

Replace the bid tabs dated February 7, 2017 with the bid tabs dated February 13, 2017.

CAD Files

The AutoCAD files for the project are being made available to prospective bidders for assistance in generating their bids. The files are available for download from the City's website.

* * * * *

Addendum Approved By:

Paul A. Hammersmith, PE
Director of Engineering/City Engineer

02-14-2017
Date

* * * * *

**Terminus for Addendum No. 1
Certification by Bidder**

Bidder shall sign and date one copy of this Addendum No. 1 and submit with his proposal as evidence of receipt and evaluation of same in his bid analysis.

Signed: _____ **Date:** _____

Company: _____

BID SCHEDULE

BIDDER agrees to perform all work described in the CONTRACT DOCUMENTS for the following unit prices:

Mid-Century Neighborhood Street Improvements

CITY OF DUBLIN

(8)
(3) x (7)

REF NO.	(1) ITEM	(2) DESCRIPTION	(3) QUANT.	(4) UNIT	(5) LABOR (\$)	(6) MATERIAL (\$)	(7) (5)+(6) TOTAL (\$)	(8) TOTAL EXTENDED INFORMAL PRICE (\$)
ROADWAY								
1	201	CLEARING AND GRUBBING	1	LS			\$0.00	\$0.00
2	201	TREE REMOVED, 18" SIZE	29	EACH			\$0.00	\$0.00
3	201	TREE REMOVED, 30" SIZE	3	EACH			\$0.00	\$0.00
4	202	PAVEMENT REMOVED	849	SY			\$0.00	\$0.00
5	202	WALK REMOVED	136	SF			\$0.00	\$0.00
6	202	CURB AND GUTTER REMOVED	2,285	FT			\$0.00	\$0.00
7	202	PIPE REMOVED	3,394	FT			\$0.00	\$0.00
8	202	PIPE REMOVED, AS PER PLAN	306	FT			\$0.00	\$0.00
9	202	CATCH BASIN REMOVED	8	EACH			\$0.00	\$0.00
10	202	ROCK CHANNEL PROTECTION REMOVED	6	SF			\$0.00	\$0.00
11	202	HEADWALL REMOVED	8	EACH			\$0.00	\$0.00
12	203	EXCAVATION	10,736	CY			\$0.00	\$0.00
13	203	EMBANKMENT	1,201	CY			\$0.00	\$0.00
14	204	SUBGRADE COMPACTION	3,507	SY			\$0.00	\$0.00
15	204	EXCAVATION OF SUBGRADE	600	CY			\$0.00	\$0.00
16	204	GRANULAR EMBANKMENT, NO. 2 STONE	450	CY			\$0.00	\$0.00
17	204	GRANULAR EMBANKMENT, NO. 304 STONE	150	CY			\$0.00	\$0.00
18	206	LIME KILN DUST STABILIZED SUBGRADE, 12" DEEP	14,448	SY			\$0.00	\$0.00
19	206	LIME KILN DUST	430	TON			\$0.00	\$0.00
20	206	CURING COAT	14,448	SY			\$0.00	\$0.00
21	206	TEST ROLLING	8	HOUR			\$0.00	\$0.00
22	206	MIXTURE DESIGN FOR CHEMICALLY STABILIZED SOILS	1	LS			\$0.00	\$0.00
23	608	4" CONCRETE WALK, AS PER PLAN	38,559	SF			\$0.00	\$0.00
24	608	CONCRETE STEPS	9	FT			\$0.00	\$0.00
25	608	CURB RAMP	8	EACH			\$0.00	\$0.00
26	625	CONDUIT, 725.051, 2", AS PER PLAN	69	FT			\$0.00	\$0.00
27	653	TOPSOIL FURNISHED AND PLACED, AS PER PLAN	1,295	CY			\$0.00	\$0.00
28	SPECIAL	DECORATIVE STONE COLUMN REMOVED AND RELOCATED	2	EACH			\$0.00	\$0.00
29	SPECIAL	DETECTABLE WARNING PANEL	48	SF			\$0.00	\$0.00

BID SCHEDULE

BIDDER agrees to perform all work described in the CONTRACT DOCUMENTS for the following unit prices:

**Mid-Century Neighborhood
Street Improvements**

CITY OF DUBLIN

(8)
(3) x (7)

REF NO.	(1) ITEM	(2) DESCRIPTION	(3) QUANT.	(4) UNIT	(5) LABOR (\$)	(6) MATERIAL (\$)	(7) (5)+(6) TOTAL (\$)	(8) TOTAL EXTENDED INFORMAL PRICE (\$)
30	SPECIAL	LIGHT POST WITH BRICK COLUMN REMOVED AND RELOCATED	2	EACH			\$0.00	\$0.00
31	SPECIAL	MAILBOX SUPPORT SYSTEM	4	EACH			\$0.00	\$0.00
32	SPECIAL	MAILBOX REMOVED AND DELIVERED	3	EACH			\$0.00	\$0.00
33	SPECIAL	MAILBOX REMOVED AND RESET	72	EACH			\$0.00	\$0.00
34	SPECIAL	MONITORING WELL, ABANDONED	1	EACH			\$0.00	\$0.00
35	SPECIAL	PROOF SURVEY	1	LS			\$0.00	\$0.00
36	SPECIAL	STONE WALL RELOCATED	2	EACH			\$0.00	\$0.00
37	SPECIAL	STONE WALL REMOVED	11	FT			\$0.00	\$0.00
38	SPECIAL	STONE WALL REMOVED AND REBUILT	1	LS			\$0.00	\$0.00
39	SPECIAL	STONE WALL REMOVED AND RESET	1	LS			\$0.00	\$0.00
40	SPECIAL	INVISIBLE DOG FENCE RESTORED	1	LS			\$0.00	\$0.00
<i>ROADWAY SUBTOTAL =</i>								<i>\$0.00</i>
EROSION CONTROL								
41	207	INLET PROTECTION	87	EACH			\$0.00	\$0.00
42	207	PERIMETER FILTER FABRIC FENCE	600	FT			\$0.00	\$0.00
43	207	CONSTRUCTION SEEDING AND MULCHING	3,886	SY			\$0.00	\$0.00
44	601	ROCK CHANNEL PROTECTION, TYPE C, WITH FILTER	2	CY			\$0.00	\$0.00
45	659	VEGETATION (SEED/MULCH), AS PER PLAN	15,542	SY			\$0.00	\$0.00
46	659	WATER FOR IRRIGATION, AS PER PLAN	252	M GAL			\$0.00	\$0.00
47	SPECIAL	TREE PROTECTION FENCE	1,000	FT			\$0.00	\$0.00
<i>EROSION CONTROL SUBTOTAL =</i>								<i>\$0.00</i>
DRAINAGE								
48	602	CONCRETE MASONRY	0.3	CY			\$0.00	\$0.00
49	603	4" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	750	FT			\$0.00	\$0.00
50	603	3" CONDUIT, TYPE E	2,025	FT			\$0.00	\$0.00
51	603	6" CONDUIT, TYPE E	99	FT			\$0.00	\$0.00
52	604	TYPE "C" MANHOLE (AA-S102)	31	EACH			\$0.00	\$0.00

BID SCHEDULE

BIDDER agrees to perform all work described in the CONTRACT DOCUMENTS for the following unit prices:

Mid-Century Neighborhood Street Improvements

CITY OF DUBLIN

(8)
(3) x (7)

REF NO.	(1) ITEM	(2) DESCRIPTION	(3) QUANT.	(4) UNIT	(5) LABOR (\$)	(6) MATERIAL (\$)	(7) (5)+(6) TOTAL (\$)	TOTAL EXTENDED INFORMAL PRICE (\$)
53	604	STANDARD CURB AND GUTTER INLET (AA-S125A)	56	EACH			\$0.00	\$0.00
54	604	DOUBLE CURB AND GUTTER INLET (AA-S125B)	9	EACH			\$0.00	\$0.00
55	604	STANDARD CATCH BASIN (AA-S133A)	2	EACH			\$0.00	\$0.00
56	604	60" CURB INLET (AA-S123)	1	EACH			\$0.00	\$0.00
57	604	CATCH BASIN RECONSTRUCTED TO GRADE, AS PER PLAN	1	EACH			\$0.00	\$0.00
58	604	CATCH BASIN RECONSTRUCTED TO GRADE	1	EACH			\$0.00	\$0.00
59	604	MANHOLE ADJUSTED TO GRADE	4	EACH			\$0.00	\$0.00
60	604	12" ADS YARD DRAIN	4	EACH			\$0.00	\$0.00
61	605	4" PIPE UNDERDRAIN (720.01)	8,700	FT			\$0.00	\$0.00
62	*611	6" SLOTTED DRAIN, TYPE 2	11	FT			\$0.00	\$0.00
63	*611	CATCH BASIN, NO. 6	1	EACH			\$0.00	\$0.00
64	*611	MANHOLE, NO. 3 WITH 108" BASE I.D. AND 12" WEIR	1	EACH			\$0.00	\$0.00
65	*895	MANUFACTURED WATER QUALITY STRUCTURE, TYPE 4	1	EACH			\$0.00	\$0.00
66	901	12" PIPE, WITH TYPE 1 BEDDING WITH ITEM 912 COMPACTED GRANULAR MATERIAL	1,867	LF			\$0.00	\$0.00
67	901	15" PIPE, WITH TYPE 1 BEDDING WITH ITEM 912 COMPACTED GRANULAR MATERIAL	1,648	LF			\$0.00	\$0.00
68	901	18" PIPE, WITH TYPE 1 BEDDING WITH ITEM 912 COMPACTED GRANULAR MATERIAL	2,037	LF			\$0.00	\$0.00
69	901	24" PIPE, WITH TYPE 1 BEDDING WITH ITEM 912 COMPACTED GRANULAR MATERIAL	44	LF			\$0.00	\$0.00
70	SPECIAL	CATCH BASIN, CAPPED WITH REINFORCED CONCRETE SLAB	1	EACH			\$0.00	\$0.00
							<i>DRAINAGE SUBTOTAL =</i>	<i>\$0.00</i>
		PAVEMENT						
71	254	3" PAVEMENT PLANING, ASPHALT CONCRETE	74	SY			\$0.00	\$0.00
72	301	3" BITUMINOUS AGGREGATE BASE	2,472	TON			\$0.00	\$0.00
73	304	AGGREGATE BASE	2,631	CY			\$0.00	\$0.00

BID SCHEDULE

BIDDER agrees to perform all work described in the CONTRACT DOCUMENTS for the following unit prices:

Mid-Century Neighborhood Street Improvements

CITY OF DUBLIN

(8)
(3) x (7)

REF NO.	(1) ITEM	(2) DESCRIPTION	(3) QUANT.	(4) UNIT	(5) LABOR (\$)	(6) MATERIAL (\$)	(7) (5)+(6) TOTAL (\$)	(8) TOTAL EXTENDED INFORMAL PRICE (\$)
74	407	NTSS-IHM TRACKLESS TACK COAT FOR INTERMEDIATE COURSE @ 0.05 GAL/SY	745	GAL			\$0.00	\$0.00
75	448	1.25" ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (MEDIUM TRAFFIC), PG64-22	1,036	TON			\$0.00	\$0.00
76	448	1.75" ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 2 (MEDIUM TRAFFIC), PG64-22	1,450	TON			\$0.00	\$0.00
77	448	2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (MEDIUM TRAFFIC), PG64-22 (DRIVEWAYS)	135	TON			\$0.00	\$0.00
78	452	6" NON-REINFORCED CONCRETE PAVEMENT	2,235	SY			\$0.00	\$0.00
79	609	6" COMBINATION CURB AND GUTTER, AS PER PLAN	12,057	FT			\$0.00	\$0.00
80	609	CURB, STRAIGHT 18"	140	FT			\$0.00	\$0.00
							<i>PAVEMENT SUBTOTAL = \$0.00</i>	
		WATER WORK						
81	801	6 INCH WATER PIPE AND FITTINGS	145	LF			\$0.00	\$0.00
82	801	8 INCH WATER PIPE AND FITTINGS	5,035	LF			\$0.00	\$0.00
83	802	6 INCH VALVE AND APPURTENANCES	16	EACH			\$0.00	\$0.00
84	802	8 INCH VALVE AND APPURTENANCES	7	EACH			\$0.00	\$0.00
85	805	1 INCH WATER SERVICE TAP, COMPLETE	3	EACH			\$0.00	\$0.00
86	805	3/4 INCH WATER SERVICE TAP, TRANSFERRED	73	EACH			\$0.00	\$0.00
87	805	CURB BOX	10	EACH			\$0.00	\$0.00
88	807	VALVE BOX ADJUST TO GRADE	1	EACH			\$0.00	\$0.00
89	807	SERVICE BOX ADJUST TO GRADE	2	EACH			\$0.00	\$0.00
90	809	FIRE HYDRANT	16	EACH			\$0.00	\$0.00
91	SPECIAL	LOCATE EXISTING WATER SERVICES	25	HOUR			\$0.00	\$0.00
92	SPECIAL	SURVEY COORDINATES	1	LS			\$0.00	\$0.00
							<i>WATER WORK SUBTOTAL = \$0.00</i>	

BID SCHEDULE

BIDDER agrees to perform all work described in the CONTRACT DOCUMENTS for the following unit prices:

**Mid-Century Neighborhood
Street Improvements**

CITY OF DUBLIN

(8)
(3) x (7)

REF NO.	(1) ITEM	(2) DESCRIPTION	(3) QUANT.	(4) UNIT	(5) LABOR (\$)	(6) MATERIAL (\$)	(7) (5)+(6) TOTAL (\$)	(8) TOTAL EXTENDED INFORMAL PRICE (\$)
SANITARY SEWER								
93	604	MANHOLE ADJUSTED TO GRADE	13	EACH			\$0.00	\$0.00
94	604	MANHOLE RECONSTRUCTED TO GRADE	1	EACH			\$0.00	\$0.00
95	901	6" PIPE, WITH TYPE 1 BEDDING WITH ITEM 912 COMPACTED GRANULAR MATERIAL	100	LF			\$0.00	\$0.00
<i>SANITARY SEWER SUBTOTAL =</i>								<i>\$0.00</i>
LIGHTING								
96	625	CONNECTOR KIT, TYPE III, UNFUSED	23	EACH			\$0.00	\$0.00
97	625	CONNECTOR KIT, TYPE II, FUSED	4	EACH			\$0.00	\$0.00
98	625	LIGHT POLE, 35', GENERAL STREET LIGHT	4	EACH			\$0.00	\$0.00
99	625	LIGHT POLE FOUNDATION, 24" X 7", AS PER PLAN	4	EACH			\$0.00	\$0.00
100	625	TRANSFORMER BASE	4	EACH			\$0.00	\$0.00
101	625	DISTRIBUTION CABLE (#4 AWG, 600V)	990	FT			\$0.00	\$0.00
102	625	POLE AND BRACKET CABLE (#12 AWG, 600V)	480	FT			\$0.00	\$0.00
103	625	CONDUIT 2" PVC, 725.051 (PVC SCH. 40)	119	FT			\$0.00	\$0.00
104	625	LUMINAIRE, 60 LED, TYPE III, MEDIUM, AS PER PLAN	1	EACH			\$0.00	\$0.00
105	625	LUMINAIRE, 80 LED, TYPE III, MEDIUM, AS PER PLAN	3	EACH			\$0.00	\$0.00
106	625	TRENCH	119	FT			\$0.00	\$0.00
107	625	GROUND ROD	8	EACH			\$0.00	\$0.00
108	625	PLASTIC, METALIZED CAUTION TAPE	119	FT			\$0.00	\$0.00
109	625	CADWELD CONNECTION	8	EACH			\$0.00	\$0.00
110	625	PULL BOX, 725.06 (18" X 11" X 18")	5	EACH			\$0.00	\$0.00
111	632	POWER SERVICE, AS PER PLAN	4	EACH			\$0.00	\$0.00
<i>LIGHTING SUBTOTAL =</i>								<i>\$0.00</i>

BID SCHEDULE

BIDDER agrees to perform all work described in the CONTRACT DOCUMENTS for the following unit prices:

Mid-Century Neighborhood Street Improvements

CITY OF DUBLIN

(8)
(3) x (7)

REF NO.	(1) ITEM	(2) DESCRIPTION	(3) QUANT.	(4) UNIT	(5) LABOR (\$)	(6) MATERIAL (\$)	(7) (5)+(6) TOTAL (\$)	(8) TOTAL EXTENDED INFORMAL PRICE (\$)
TRAFFIC CONTROL								
112	630	GROUND MOUNTED SUPPORT, NO. 3 POST, AS PER PLAN	129.1	FT			\$0.00	\$0.00
113	630	SIGN POST REFLECTOR	2	EACH			\$0.00	\$0.00
114	630	SIGN, STREET NAME, AS PER PLAN	8	EACH			\$0.00	\$0.00
115	630	SIGN, FLAT SHEET	40.8	SF			\$0.00	\$0.00
116	630	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE, AS PER PLAN	17	EACH			\$0.00	\$0.00
117	630	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	12	EACH			\$0.00	\$0.00
118	630	REMOVAL OF GROUND MOUNTED ANCHOR POST SUPPORT AND DISPOSAL	4	EACH			\$0.00	\$0.00
119	630	SIGNING, MISC.: 2-1/4" SQUARE ANCHOR POST	12	EACH			\$0.00	\$0.00
120	644	STOP LINE	25	FT			\$0.00	\$0.00
<i>TRAFFIC CONTROL SUBTOTAL =</i>								<i>\$0.00</i>
MAINTENANCE OF TRAFFIC								
121	410	TRAFFIC COMPACTED SURFACE, TYPE A OR B	1700	CY			\$0.00	\$0.00
122	614	LAW ENFORCEMENT OFFICER WITH PATROL CAR, AS PER PLAN	80	HOUR			\$0.00	\$0.00
123	615	ROADS FOR MAINTAINING TRAFFIC	1	LS			\$0.00	\$0.00
124	616	WATER	100	MGAL			\$0.00	\$0.00
<i>MAINTENANCE OF TRAFFIC SUBTOTAL =</i>								<i>\$0.00</i>
LANDSCAPING								
125	661	DECIDUOUS TREE 2" CAL. SYRINGA RETICULATA 'IVORY SILK' JAPANESE TREE LILAC	60	EACH			\$0.00	\$0.00
126	661	DECIDUOUS TREE 2" CAL. CLADRASTIS KENTUKEA YELLOWWOOD	54	EACH			\$0.00	\$0.00

BID SCHEDULE

BIDDER agrees to perform all work described in the CONTRACT DOCUMENTS for the following unit prices:

Mid-Century Neighborhood Street Improvements

CITY OF DUBLIN

(8)
(3) x (7)

REF NO.	(1) ITEM	(2) DESCRIPTION	(3) QUANT.	(4) UNIT	(5) LABOR (\$)	(6) MATERIAL (\$)	(7) (5)+(6) TOTAL (\$)	(8) TOTAL EXTENDED INFORMAL PRICE (\$)
127	661	DECIDUOUS TREE 2" CAL. MALUS SPP. 'SUGAR TYME' SUGAR TYME CRABAPPLE	33	EACH			\$0.00	\$0.00
128	661	DECIDUOUS TREE 2" CAL. QUERCUS RUBRA RED OAK	35	EACH			\$0.00	\$0.00
129	661	DECIDUOUS TREE 2" CAL. LIRIODENDRON TULIPIFERA TULIPTREE	27	EACH			\$0.00	\$0.00
130	661	DECIDUOUS TREE 2" CAL. HALESIA CAROLINA CAROLINA SILVERBELL	18	EACH			\$0.00	\$0.00
131	661	DECIDUOUS SHRUB, 36", TAXUS X MEDIA 'DENSIFORMIS'	3	EACH			\$0.00	\$0.00
132	SPECIAL	TREE WATERING BAG	227	EACH			\$0.00	\$0.00
<i>LANDSCAPING SUBTOTAL =</i>								<i>\$0.00</i>
INCIDENTALS								
133	108.03	TYPE B CPM PROGRESS SCHEDULE	1	LS			\$0.00	\$0.00
134	614	MAINTAINING TRAFFIC	1	LS			\$0.00	\$0.00
135	623	CONSTRUCTION LAYOUT STAKES	1	LS			\$0.00	\$0.00
136	624	MOBILIZATION	1	LS			\$0.00	\$0.00
<i>INCIDENTALS SUBTOTAL =</i>								<i>\$0.00</i>

* DENOTES OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS (2016 EDITION).

GRAND TOTAL = \$0.00

TOTAL BID FOR PROJECT: _____
SUBMITTING CONTRACTOR: _____