

BEFORE DEMOLITION / CONSTRUCTION. CONTRACTOR TO COORDINATE WITH ALL SERVICE PROVIDERS, DETERMINE POINTS OF CONNECTION, ROUTING AND LOCATION OF WHERE UTILITIES WILL ENTER THE BUILDING BEFORE CONSTRUCTION.



FLOODPLAIN DATA

ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY'S FLOOD INSURANCE RATE MAP (DATED JUNE 17, 2008), THE SUBJECT PARCELS LIE WITHIN ZONE "X", COMMUNITY PANEL NO. 39049C0151K

BASIS OF INFORMATION

ALL EXISTING CONDITIONS, TOPOGRAPHY, UTILITIES, & EASEMENTS ARE AS TAKEN FROM A SURVEY PROVIDED BY LANDMARK SURVEY GROUP

PER SURVEY NOTES, BEARINGS ARE BASED ON THE OHIO STATE PLANE COORDINATE SYSTEM, SOUTH ZONE, NAD83(CORS)

CONTACT INFORMATION

ARCHITECT

RICHARD TAYLOR 48 S. HIGH ST SUITE B **DUBLIN, OH 43017** (614) 766-7257

SURVEYOR

LANDMARK SURVEY GROUP RICHARD TAYLOR ARCHITECTS 690 LAKEVIEW PLAZA BLVD. SUITE A WORTHINGTON OH 43085 614-485-9000 SCOTT GRUNDEI

EXISTING TREE TO BE REMOVED

EXISTING HOUSE TO RELOCATED. NEW FOUNDATION TO BE INSTALLED, SEE ARCHITECTURAL PLANS FOR DETAILS

EXISTING STONE WALL TO BE REPAIRED

PROPOSED HOUSE ADDITION

PROPOSED ASPHALT DRIVE. APPROACH TO BE INSTALLED PER CITY OF DUBLIN STANDARD **DRAWING RD-07**

PROPOSED BRICK PAVER WALK.

PROPOSED TRENCH DRAIN. TRENCH OUTLET PIPE TO BE CONNECTED TO DOWNSPOUT DRAIN.

CONTRACTOR TO DETERMINE LAYOUT/ CONNECTION IN FIELD.

GENERAL NOTES

THE INFORMATION DEPICTED ON THESE CONSTRUCTION DOCUMENTS IS AS ACCURATE AS POSSIBLE WITH REGARD TO THE INFORMATION PROVIDED BY THE SURVEYOR, ARCHITECT AND CITY GIS. IT IS THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY ALL EXISTING AND

PROPOSED GRADES AND UTILITIES PRIOR TO CONSTRUCTION. NOTIFY THE OWNER'S REPRESENTATIVE AND THE BUILDING DESIGNER IMMEDIATELY OF ANY DISCREPANCY FOUND BETWEEN THE FIELD CONDITIONS AND THESE PLANS.

ALL PROPOSED SPOT ELEVATIONS AND CONTOURS SHOWN ON THE PLAN ARE PROPOSED FINISHED GRADES. IT IS THE CONTRACTORS RESPONSIBILITY TO ADJUST SUBGRADE ELEVATIONS ACCORDINGLY TO ENSURE POSITIVE DRAINAGE AWAY FROM FOUNDATIONS TO MEET OR EXCEED STATE AND/OR LOCAL REQUIREMENTS. THE GRADE FROM FOUNDATION

CONTRACTOR TO INSTALL ALL NECESSARY EROSION CONTROL MEASURES PRIOR TO THE START C OF ANY GRADING ACTIVITIES. PERMANENT EROSION CONTROL, TURF ESTABLISHMENT, AND SOIL

STABILIZATION IS THE RESPONSIBILITY OF THE CONTRACTOR. ALL CONSTRUCTION SHALL COMPLY WITH APPLICABLE CODES AND LOCAL REQUIREMENTS. CONTRACTORS MUST COMPLY WITH CONTRACTOR REGISTRATION REQUIREMENTS OF ALL

GOVERNING AUTHORITIES. ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE ACQUIRED. ALL WORK SHALL MEET JURISDICTIONAL REQUIREMENTS AND SPECIFICATIONS.

CONTRACTOR IS RESPONSIBLE FOR TRAFFIC CONTROL WHILE WORKING IN THE PUBLIC RIGHT OF WAY OR ADJOINING PROPERTIES.

CONTAIN ARCHITECTURAL STRUCTURES. CONTRACTOR IS RESPONSIBLE FOR VERIFYING INFORMATION SHOWN COORDINATE WITH THE ARCHITECTURAL PLANS BEFORE CONSTRUCTION. CONTRACTOR TO NOTIFY OWNER'S REPRESENTATIVE AND THE BUILDING DESIGNER IMMEDIATELY OF ANY DISCREPANCY FOUND BETWEEN PLANS.

SITE DATA

SITE ADDRESS:

27 N RIVERVIEW ST. DUBLIN OHIO 43017

OWNER:

HAFFAR GROUP LLC

PARCEL:

273-000032

SITE AREA:

0.211 AC. (9,170 SF)

ZONING:

HD-HR, HISTORICAL RESIDENTIAL DISTRICT

SETBACKS:

BUILDINGS FRONT: 20'

REAR: 20% OF LOT DEPTH. PROPOSED - 20' SIDE: 3'

IMPERVIOUS AREA (WITHIN SITE P/L):

EX. HOUSE: 975 SQFT PROP. HOUSE ADDITION: 1,775 SQFT


TOTAL HOUSE = 2,754 SF PROP. IMPERVIOUS PAVEMENT (DRIVE & WALK): 535 SQFT

PROPOSED COVERAGE (EXCLU. ROADWAY)= 35.9% ((2,754+535)/9,170)

EX. IMPERVIOUS INSIDE P/L (N RIVERVIEW ROADWAY): 1,032 SQFT

PROPOSED COVERAGE (INCL. N RIVERVIEW ROADWAY) = 47.1% ((2,754+535+1,032)/9,170)

PLAN LEGEND
EXISTING CONTOURS
PROPOSED CONTOURS
EXISTING SPOT GRADE
PROPOSED SPOT ELEVATION
PROPOSED SLOPE
PROPOSED ADDITION (2,774 SF)
PROPOSED DRIVE (428 SF)
PROPOSED BRICK WALK (142 SF)



CHECKED: SHEET NO.

05/09/2024

JOB NO.: 2024-18

DESIGN:

PLANS PREPARED FOR:

PLANS PREPARED BY:

E:\CURRENT PROJECTS\2024\2024-19_RICHTAYLOR-27 N RIVERVIEW\02-CIVIL\DESIGN\27 N RIVERVIEW - SITE PLAN.DWG - 5/9/2024 2:27 PM