



2025 Wall Maintenance Scope of Work

November 6, 2025

The following stone walls are scheduled for maintenance repairs in the Fall – Winter of 2025.

Description of Work

Repair the 15 identified walls in kind based on the information below. An interactive map and individual photos for each work location are included as links below. Reuse stone whenever possible, if new stones are required the stones shall match as closely as possible to the original stone with approval by the City.

[Interactive map link](#)

[Location Photos link](#) (password = 70XV69YPQJht)

Repair Locations

- 244111 - replace facing stone
- 244294 - Realign and secure 3-foot top course cracked or missing stone
- 244296 - 1 LF on both wall ends for 2 lf total of repair
- 244304 - Adjacent to w bridge st at cemetery, 3 ft
- 244307 - Area in middle bulging and eroded, 5 ft
- 244327 - Base block broken and mortar too at east bridge st and north blacksmith, 3 ft
- 244328 - 8 wall deficiencies, 37 ft
- 244340 - Entire wall several areas of wall failure
- 244379 - 3,3,3,3,10 = 22 lf of repairs
- 244381 - one small bulge by ramp, 4 ft
- 244382 - 6,6,4= 16 ft of spot repairs
- 244384 - 7 ft long spot failure
- 244416 - 4-foot section and 6-foot of facing stone repair and capstone, 10 ft
- 244476 - 15, 10 = 25 ft spot repairs
- 244477 - 4,4= 8 ft, 2 repairs at both ends of wall

Completion Date April 30, 2026

Quote Due Date: Email to the Project Manager by 12:00 pm on Friday November 21, 2025.
All work shall be paid in prevailing wage.

Project Manager Robert Taylor, PE

rjtaylor@dublin.oh.us

614.410.4775