



Project Description / Narrative

Scope of work is to remove 1 existing chimney located at 6138 Turvey Loop E from rear of the existing building. The existing chimney is cantilevered from the floor and has no foundation under the chimney. The chimney has cultured stone on the exterior walls of the chimney. The weight of the stone is causing the floor joists to sag on the exterior which is causing the floor joists under the Great Room to heave upwards which has created a hump in the Great Room floor.