


COMPLIANCE CODE



### **AMERICAN TOWER®**

ATC SITE NAME: DUBLIN OH ATC SITE NUMBER: 307538

AT&T PACE NUMBER: MROWP052577, MROWP051977

AT&T SITE ID: OHL03059 AT&T FA CODE:10011704 AT&T SITE NAME: DUBLIN

PROJECT SUMMARY

SITE ADDRESS: 5780 SHIER-RINGS ROAD

**DUBLIN, OH 43017** 



**LOCATION MAP** 

SHEET INDEX

# AT&T MOBILITY ANTENNA AMENDMENT DRAWINGS

PROJECT DESCRIPTION

								1 1
ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE	SITE ADDRESS:	THE PROPOSED PROJECT INCLUDES MODIFYING GROUND BASED AND TOWER MOUNTED EQUIPMENT AS INDICATED PER BELOW:	SHEET NO:	DESCRIPTION:	REV:	DATE:	BY:	Ш
FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNMENT AUTHORITIES. NOTHING IN THESE PLANS IS	5780 SHIER-RINGS ROAD	TOWER WORK: REMOVE (3) ANTENNA(s) AND (2) #8 AWG DC CABLE(s)	G-001	COVER SHEET	0	06/25/21	RC	1 t
TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.	DUBLIN, OH 43017	INSTALL (3) ANTENNA(s), (2) #6 AWG DC CABLE(s)	G-002	GENERAL NOTES	0	06/25/21	RC	11
2017 OHIO BUILDING CODE (OBC)	COUNTY: FRANKLIN  GEOGRAPHIC COORDINATES:	EXISTING (9) ANTENNA(s), (12) RRH(s), (3) SQUID(s), (12) 1-5/8"	C-101	DETAILED SITE PLAN	0	06/25/21	RC	11
2. 2017 NATIONAL ELECTRIC CODE (NEC)	LATITUDE: 40.0970000	COAX CABLE(s), (1) 12 PAIR FIBER TRUNK AND (1) 18 PAIR FIBER	C-102	DETAILED EQUIPMENT LAYOUT	0	06/25/21	RC	11
3. LOCAL BUILDING CODE 4. CITY/COUNTY ORDINANCES	LONGITUDE: -83.1402800	TRUNK AND (4) #6 AWG DC CABLE(s) TO REMAIN GROUND WORK:	C-201	TOWER ELEVATION	0	06/25/21	RC	
	GROUND ELEVATION: 906' AMSL	INSTALL (3) ABIA, (1) ASIA, (3) ABIL, (1) ASIK EXISTING (12) DIPLEXER TO REMAIN	C-401	CURRENT ANTENNA PLAN AND EXISTING ANTENNA SCHEDULE	0	06/25/21	RC	
			C-402	PROPOSED ANTENNA PLAN AND FINAL ANTENNA SCHEDULE	0	06/25/21	RC	14
			C-501	CONSTRUCTION DETAILS	0	06/25/21	RC	Ш
	PROJECT TEAM	PROJECT NOTES	E-501	GROUNDING DETAILS	0	06/25/21	RC	ΙĻ
	TOWER OWNER: APPLICANT:	THE FACILITY IS UNMANNED.	R-601	SUPPLEMENTAL				Ш
	AMERICAN TOWER AT&T MOBILITY	A TECHNICIAN WILL VISIT THE SITE APPROXIMATELY ONCE     A MONTH FOR ROUTINE INSPECTION AND MAINTENANCE.	R-602	SUPPLEMENTAL				Ш
	10 PRESIDENTIAL WAY WOBURN, MA 01801	THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT LAND DISTURBANCE OR EFFECT OF STORM WATER DRAINAGE.	R-603	SUPPLEMENTAL				
UTILITY COMPANIES	ARCHITECT (COORDIATING	NO SANITARY SEWER, POTABLE WATER OR TRASH DISPOSAL IS REQUIRED.	R-604	SUPPLEMENTAL				╽┞
POWER COMPANY: TBD	PROFESSIONAL):	5. HANDICAP ACCESS IS NOT REQUIRED.	R-605	SUPPLEMENTAL				] }
PHONE: TBD TELEPHONE COMPANY: TBD	PETER LICHOMSKI, AIA 49030 PONTIAC TRAIL. SUITE 400.	PROJECT LOCATION DIRECTIONS		SUPPLEMENTAL				
PHONE: TBD	WIXOM, MI 48393 PH: (248) 705-9212		R-607	SUPPLEMENTAL				┇┞
Know what's below. Call before you dig.	PH: (248) 705-9212  PROPERTY OWNER:  TBD	FROM 4199 WEAVER CT. S HILLIARD, OHDRIVE NORTH ON WEAVER CT. STHEN TURN LEFT ON NORTHWEST PKWYTURN RIGHT ON AVERY RDCONTINUE NORTH ON AVERY RD.TURN RIGHT ON SHEIR RINGS RD.CONTINUE ON SHEIR RINGS RD APPROX 3 TO 4 MILESSITE IS ON LEFT BEHIND STANLEY STEAMER						





49030 Pontiac Trail, Suite 40 Wixom, Michigan 48393 PHONE: (248) 705-9212

REV.	DESCRIPTION	BY	DATE
$\mathbb{A}_{-}$	PRELIM	RC	04/09/21
<u></u>	FINAL CD	RC	06/25/21
$A_{-}$			
$\overline{\wedge}$			
$I \overline{\wedge}$			
	REV.	A PRELIM	A PRELIM RC

ATC SITE NUMBER:

307538


ATC SITE NAME:

**DUBLIN OH** 

AT&T MOBILITY SITE NAME:

DUBLIN

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN. OH 43017



NAME: PETER LICHOMSKI LICENSE NO: |4|6266 EXP DATE: |2/3|/202|



DATE DRAWN: 04/06/21
ATC JOB NO: 13619927
CUSTOMER ID: OHL03059
CUSTOMER NAME: MROWP052577

**COVER SHEET** 

SHEET NUMBER

G-001

0

### **GENERAL CONSTRUCTION NOTES:**

- OWNER FURNISHED MATERIALS, AT&T MOBILITY "THE COMPANY" WILL PROVIDE AND THE 22. CONTRACTOR WILL INSTALL
- A. BTS EQUIPMENT FRAME (PLATFORM) AND ICEBRIDGE SHELTER (GROUND
- BUILD/CO-LOCATE ONLY) AC/TELCO INTERFACE BOX (PPC)
- C. ICE BRIDGE (CABLE TRAY WITH COVER) (GROUND BUILD/CO-LOCATE ONLY, GC TO FURNISH AND INSTALL FOR ROOFTOP INSTALLATION)
- D. TOWERS, MONOPOLES
- TOWER LIGHTING GENERATORS & LIQUID PROPANE TANK
- ANTENNA STANDARD BRACKETS, FRAMES AND PIPES FOR MOUNTING
- ANTENNAS (INSTALLED BY OTHERS)
- TRANSMISSION LINE
- TRANSMISSION LINE JUMPERS
- TRANSMISSION LINE CONNECTORS WITH WEATHERPROOFING KITS
- TRANSMISSION LINE GROUND KITS
- HANGERS
- HOISTING GRIPS
- O. BTS EQUIPMENT
- THE CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL OTHER MATERIALS FOR THE COMPLETE INSTALLATION OF THE SITE INCLUDING, BUT NOT LIMITED TO, SUCH
  MATERIALS AS FENCING, STRUCTURAL STEEL SUPPORTING SUB-FRAME FOR PLATFORM ROOFING LABOR AND MATERIALS GROUNDING RINGS GROUNDING WIRES COPPER-CLAD OR XIT CHEMICAL GROUND ROD(S), BUSS BARS, TRANSFORMERS AND DISCONNECT SWITCHES WHERE APPLICABLE, TEMPORARY ELECTRICAL POWER, CONDUIT, LANDSCAPING COMPOUND STONE, CRANES, CORE DRILLING, SLEEPERS AND RUBBER MATTING, REBAR, CONCRETE CAISSONS, PADS AND/OR AUGER MOUNTS,
  MISCELLANEOUS FASTENERS, CABLE TRAYS, NON-STANDARD ANTENNA FRAMES AND ALL OTHER MATERIAL AND LABOR REQUIRED TO COMPLETE THE JOB ACCORDING TO THE DRAWINGS AND SPECIFICATIONS. IT IS THE POSITION OF AT&T MOBILITY TO APPLY FOR PERMITTING AND CONTRACTOR RESPONSIBLE FOR PICKUP AND PAYMENT OF
- ALL WORK SHALL CONFORM TO ALL CURRENT APPLICABLE FEDERAL, STATE, AND LOCAL CODES, INCLUDING ANSI/EIA/TIA-222, AND COMPLY WITH ATC CONSTRUCTION
- CONTRACTOR SHALL CONTACT LOCAL 811 FOR IDENTIFICATION OF UNDERGROUND
- CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED
- ALL DIMENSIONS TO, OF, AND ON EXISTING BUILDINGS, DRAINAGE STRUCTURES, AND SITE IMPROVEMENTS SHALL BE VERIFIED IN FIELD BY CONTRACTOR WITH ALL DISCREPANCIES REPORTED TO THE ENGINEER.
- DO NOT CHANGE SIZE OR SPACING OF STRUCTURAL ELEMENTS
- DETAILS SHOWN ARE TYPICAL; SIMILAR DETAILS APPLY TO SIMILAR CONDITIONS UNLESS 32.
- THESE DRAWINGS DO NOT INCLUDE NECESSARY COMPONENTS FOR CONSTRUCTION SAFETY WHICH SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR
- CONTRACTOR SHALL BRACE STRUCTURES UNTIL ALL STRUCTURAL ELEMENTS NEEDED 33. FOR STABILITY ARE INSTALLED. THESE ELEMENTS ARE AS FOLLOWS: LATERAL BRACING,
- CONTRACTOR SHALL DETERMINE EXACT LOCATION OF EXISTING UTILITIES, GROUNDS DRAINS, DRAIN PIPES, VENTS, ETC, BEFORE COMMENCING WORK
- INCORRECTLY FABRICATED, DAMAGED, OR OTHERWISE MISFITTING OR NONCONFORMING MATERIALS OR CONDITIONS SHALL BE REPORTED TO THE AT&T MOBILITY REP PRIOR TO REMEDIAL OR CORRECTIVE ACTION. ANY SUCH REMEDIAL ACTION SHALL REQUIRE WRITTEN APPROVAL BY THE AT&T MOBILITY REP PRIOR TO
- EACH CONTRACTOR SHALL COOPERATE WITH THE AT&T MOBILITY REP, AND OORDINATE HIS WORK WITH THE WORK OF OTHERS
- CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED BY CONSTRUCTION OF THIS PROJECT TO MATCH EXISTING PRE-CONSTRUCTION CONDITIONS TO THE SATISFACTION OF THE AT&T MOBILITY CONSTRUCTION MANAGER
- ALL CABLE/CONDUIT ENTRY/EXIT PORTS SHALL BE WEATHERPROOFED DURING
- WHERE EXISTING CONDITIONS DO NOT MATCH THOSE SHOWN IN THIS PLAN SET, CONTRACTOR SHALL NOTIFY THE AT&T MOBILITY REP AND ENGINEER OF RECORD
- CONTRACTOR SHALL ENSURE ALL SUBCONTRACTORS ARE PROVIDED WITH A COMPLETE AND CURRENT SET OF DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT.
- CONTRACTOR SHALL REMOVE ALL RUBBISH AND DEBRIS FROM THE SITE AT THE END OF
- CONTRACTOR SHALL COORDINATE WORK SCHEDULE WITH AMERICAN TOWER CORPORATION (ATC) AND TAKE PRECAUTIONS TO MINIMIZE IMPACT AND DISRUPTION OF OTHER OCCUPANTS OF THE FACILITY.
- CONTRACTOR SHALL FURNISH AT&T MOBILITY AND AMERICAN TOWER CORPORATION (ATC) WITH A PDF MARKED UP AS-BUILT SET OF DRAWINGS UPON COMPLETION OF
- PRIOR TO SUBMISSION OF BID. CONTRACTOR SHALL COORDINATE WITH AT&T MOBILITY REP TO DETERMINE WHAT, IF ANY, ITEMS WILL BE PROVIDED. ALL ITEMS NOT PROVIDED SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR. CONTRACTOR WILL INSTALL 2. ALL EXTERIOR #6 GREED GROUND WIRE "DAISY CHAIN" CONNECTIONS ARE TO BE

- ALL ITEMS PROVIDED.
- PRIOR TO SUBMISSION OF BID. CONTRACTOR SHALL COORDINATE WITH AT&T MOBILITY REP TO DETERMINE IF ANY PERMITS WILL BE OBTAINED BY CONTRACTOR. ALL
  REQUIRED PERMITS NOT OBTAINED BY AT&T MOBILITY MUST BE OBTAINED, AND PAID
- 23. CONTRACTOR SHALL INSTALL ALL SITE SIGNAGE IN ACCORDANCE WITH AT&T MOBILITY
- CONTRACTOR SHALL SUBMIT ALL SHOP DRAWINGS TO AT&T MOBILITY FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.
- 25. ALL EQUIPMENT SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND LOCATED ACCORDING TO AT&T MOBILITY SPECIFICATIONS, AND AS SHOWN IN THESE PLANS.
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT.
- CONTRACTOR SHALL NOTIFY AT&T MORILITY REP A MINIMUM OF 48 HOURS IN ADVANCE OF POURING CONCRETE OR BACKFILLING ANY UNDERGROUND UTILITIES, FOUNDATIONS OR SEALING ANY WALL, FLOOR OR ROOF PENETRATIONS FOR ENGINEERING REVIEW
- CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SAFETY INCLUDING COMPLIANCE WITH ALL APPLICABLE OSHA STANDARDS AND RECOMMENDATIONS AND SHALL PROVIDE ALL NECESSARY SAFETY DEVICES INCLUDING PPE AND PPM AND CONSTRUCTION DEVICES SUCH AS WELDING AND FIRE PREVENTION, TEMPORARY SHORING, SCAFFOLDING, TRENCH BOXES/SLOPING, BARRIERS, ETC.
- THE CONTRACTOR SHALL PROTECT AT HIS OWN EXPENSE, ALL EXISTING FACILITIES AND SUCH OF HIS NEW WORK LIABLE TO INJURY DURING THE CONSTRUCTION PERIOD. ANY DAMAGE CAUSED BY NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, OR BY THE ELEMENTS DUE TO NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES. FITHER TO THE EXISTING WORK, OR TO HIS WORK OR THE WORK OF ANY OTHER CONTRACTOR, SHALL BE REPAIRED AT HIS EXPENSE TO THE OWNER'S SATISFACTION.
- 30. ALL WORK SHALL BE INSTALLED IN A FIRST CLASS, NEAT AND WORKMANLIKE MANNER BY MECHANICS SKILLED IN THE TRADE INVOLVED. THE QUALITY OF WORKMANSHIP SHALL BE SUBJECT TO THE APPROVAL OF THE AT&T MOBILITY REP. ANY WORK FOUND BY THE AT&T MOBILITY, REP TO BE OF INFERIOR QUALITY AND/OR WORKMANSHIP SHALL BE REPLACED AND/OR REWORKED AT CONTRACTOR EXPENSE UNTIL APPROVAL IS
- IN ORDER TO ESTABLISH STANDARDS OF QUALITY AND PERFORMANCE, ALL TYPES OF MATERIALS LISTED HEREINAFTER BY MANUFACTURER'S NAMES AND/OF MANUFACTURER'S CATALOG NUMBER SHALL BE PROVIDED BY THESE MANUFACTURERS
- AT&T MOBILITY FURNISHED EQUIPMENT SHALL BE PICKED-UP AT THE AT&T MOBILITY WAREHOUSE, NO LATER THAN 48HR AFTER BEING NOTIFIED INSURED, STORED, UNCRATE, PROTECTED AND INSTALLED BY THE CONTRACTOR WITH ALL APPURTENANCES REQUIRED TO PLACE THE EQUIPMENT IN OPERATION, READY FOR USE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE EQUIPMENT AFTER PICKING IT
- AT&T MOBILITY OR HIS ARCHITECT/ENGINEER RESERVES THE RIGHT TO REJECT ANY FOLIPMENT OR MATERIALS WHICH, IN HIS OWN OPINION ARE NOT IN COMPLIANCE WITH THE CONTRACT DOCUMENTS, EITHER BEFORE OR AFTER INSTALLATION AND THE EQUIPMENT SHALL BE REPLACED WITH EQUIPMENT CONFORMING TO THE REQUIREMENTS OF THE CONTRACT DOCUMENTS BY THE CONTRACTOR AT NO COST TO AT&T MOBILITY OR THEIR ARCHITECT/ENGINEER

### SPECIAL CONSTRUCTION ANTENNA INSTALLATION NOTES:

- WORK INCLUDED
  - ANTENNA AND COAXIAL CABLES ARE FURNISHED BY AT&T MOBILITY UNDER A SEPARATE CONTRACT. THE CONTRACTOR SHALL ASSIST ANTENNA INSTALLATION CONTRACTOR IN TERMS OD COORDINATION AND SITE ACCESS. ERECTION SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF
  - B. INSTALL ANTENNA AS INDICATE ON DRAWINGS AND AT&T MOBILITY
  - C. INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS
  - D. INSTALL FURNISHED GALVANIZED STEEL OR ALUMINUM WAVEGUIDE AND PROVIDE PRINTOUT OF THAT TEST.
  - E. CONTRACTOR SHALL PROVIDE FOUR (4) SETS OF SWEEP TESTS USING ANRITZU-PACKARD 8713B RF SCALAR NETWORK ANALYZER. SUBMIT FREQUENCY DOMAIN REFLECTOMETER(FDR) TESTS RESULTS TO THE PROJECT MANAGER. SWEEP TESTS SHALL BE AS PER ATTACHED RES "MINIMUM FIELD TESTING RECOMMENDED FOR ANTENNA AND HELIAX COAXIAL CABLE SYSTEMS" DATED 10/5/93. TESTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING SERVICE AND BE BOUND AND SUBMITTED WITHIN ONE WEEK OF WORK COMPLETION.
  - INSTALL COAXIAL CABLES AND TERMINATING BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS. WEATHERPROOF ALL CONNECTIONS RETWEEN THE ANTENNA AND FOLIPMENT PER MANUFACTURER'S REQUIREMENTS. TERMINATE ALL COAXIAL CABLE THREE (3) FEET IN EXCESS OF ENTRY PORT LOCATION UNLESS OTHERWISE STATED.
  - G. ANTENNA AND COAXIAL CABLE GROUNDING:

WEATHER SEALED WITH RES CONNECTORS/SPLICE WEATHERPROOFING KIT #221213 OR

ALL COAXIAL CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF COAXIAL CABLE (NOT WITHIN BENDS)

> ALL DISCREPANCIES FROM WHAT IS SHOWN ON THESE CONSTRUCTION DRAWINGS SHALL BE COMMUNICATED TO ATC ENGINEERING IMMEDIATELY FOR CORRECTION OR RE-DESIGN. FAILURE TO COMMUNICATE DIRECTLY WITH ATC ENGINEERING OR ANY CHANGES FROM THE DESIGN CONDUCTED WITHOUT PRIOR APPROVAL FROM ATC ENGINEERING SHALL BE THE SOLE RESPONSIBILITY OF THE GENERAL CONTRACTOR.





49030 Pontiac Trail. Suite Wixom, Michigan 48393 PHONE: (248) 705-9212

REV.	DESCRIPTION	BY	DATE
$\mathbb{A}_{-}$	PRELIM	RC	04/09/21
<u> </u>	FINAL CD	RC	06/25/21
$\overline{\wedge}$			
$\overline{\wedge}$			
$\overline{\wedge}$			

ATC SITE NUMBER:


307538

ATC SITE NAME:

**DUBLIN OH** 

AT&T MOBILITY SITE NAME: DUBLIN

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN, OH 43017



NAME: PETER LICHOMSKI LICENSE NO: 1416266 EXP DATE: |2/3|/202|



DATE DRAWN: 04/06/21 ATC JOB NO: 13619927 CUSTOMER ID: OHL03059 CUSTOMER NAME: MROWP052577

**GENERAL NOTES** 

SHEET NUMBER:

G-002


### SITE PLAN NOTES:


- THIS SITE PLAN REPRESENTS THE BEST PRESENT KNOWLEDGE AVAILABLE
  TO THE ENGINEER AT THE TIME OF THIS DESIGN. THE CONTRACTOR SHALL
  VISIT THE SITE PRIOR TO CONSTRUCTION AND VERIFY ALL EXISTING
  CONDITIONS RELATED TO THE SCOPE OF WORK FOR THIS PROJECT.
- 2. ICE BRIDGE, CABLE LADDER, COAX PORT, AND COAX CABLE ARE SHOWN FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM THE EXACT LOCATION OF ALL PROPOSED AND EXISTING EQUIPMENT AND STRUCTURES DEPICTED ON THIS PLAN. BEFORE UTILIZING EXISTING CABLE SUPPORTS, COAX PORTS, INSTALLING NEW PORTS OR ANY OTHER EQUIPMENT, CONTRACTOR SHALL VERIFY ALL ASPECTS OF THE COMPONENTS MEET THE ATC SPECIFICATIONS.
- 3. THIS PROJECT INCLUDES NO INSTALL OR MODIFICATION AT GRADE.

### LEGEND 8 GROUNDING TEST WELL ATS AUTOMATIC TRANSFER SWITCH BOLL ARD CSC CELL SITE CABINET D DISCONNECT ELECTRICAL **FIBER** GEN **GENERATOR** GENERATOR RECEPTACAL HH, V HAND HOLE, VAULT ΙB ICE BRIDGE KENTROX BOX LC LIGHTING CONTROL METER РΒ PULL BOX PP POWER POLE TELCO TRN TRANSFORMER CHAINLINK FENCE


### PROPOSED CABLE LENGTH:

- ESTIMATED LENGTH OF PROPOSED CABLE IS 209'. ESTIMATED LENGTH OF CABLE WAS PROVIDED BY CUSTOMER OR CALCULATED BY ADDING THE RAD CENTER AND THE DISTANCE FROM THE SHELTER ENTRY PLATE TO THE TOWER (ALONG THE ICE BRIDGE) AND A SAFETY FACTOR MEASUREMENT OF 15% (OF THE TWO PREVIOUS VALUES), CDS DEFER TO GREATEST CABLE LENGTH.
- 2. ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. IF ADEQUATE SPACE EXISTS, ROUTE CABLES THROUGH ENTRY PORT HOLE, UP INSIDE OF MONOPOLE, AND THROUGH EXIT PORT HOLE. IF ROUTING OUTSIDE THE MONOPOLE, ATTACH CABLES USING STAND-OFF ADAPTERS MOUNTED TO TOWER USING STAINLESS STEEL BANDING. ADEQUATELY SECURE CABLES USING EITHER APPROPRIATELY SIZED STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY CABLE MANUFACTURER.













49030 Pontiac Trail, Suite 400 Wixom, Michigan 48393 PHONE: (248) 705-9212

REV.	DESCRIPTION	BY	DATE
$\mathbb{A}_{-}$	PRELIM	RC	04/09/21
△_	FINAL CD	RC	06/25/21
$\triangle_{-}$			
$\overline{\wedge}$			
$\overline{\wedge}$			

ATC SITE NUMBER:

307538


ATC SITE NAME:

DUBLIN OH

AT&T MOBILITY SITE NAME:

DUBLIN

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN. OH 43017



NAME: PETER LICHOMSKI LICENSE NO: |4|6266 EXP DATE: |2/3|/202|




DATE DRAWN:	04/06/21
ATC JOB NO:	13619927
CUSTOMER ID:	OHL03059
CUSTOMER NAME:	MROWP052577

**DETAILED SITE PLAN** 


SHEET NUMBER:

C-101





- 1 ICE BRIDGE
- (2) COAX PORT
- (3) COAX TRUNK CABLE
- 4 HVAC
- (5) STOOP
- 6 DOOR
- 7) FIF RACK
- (8) (12) LGP 13513 DIPLEXERS
- (9) LADDER
- (10) ADD (3) ABIA, (1) ASIA, (3) ABIL, (1) ASIK







49030 Pontiac Trail, Suite 400 Wixom, Michigan 48393 PHONE: (248) 705-9212

l	REV.	DESCRIPTION	BY	DATE
l	$\mathbb{A}_{-}$	PRELIM	RC	04/09/21
l	<u></u>	FINAL CD	RC	06/25/21
l	$A_{-}$			
l	$\overline{\wedge}$			
l	$I \overline{\wedge}^-$			

ATC SITE NUMBER:

307538

ATC SITE NAME:

**DUBLIN OH** 

AT&T MOBILITY SITE NAME:

DUBLIN

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN, OH 43017

PETER P.
LICHOMSKI

1416266

NAME: PETER LICHOMSKI

LICENSE NO: I4|6246

EXP DATE: |2/3|/202|





	DATE DRAWN:	04/06/21
	ATC JOB NO:	13619927
	CUSTOMER ID:	OHL03059
	CUSTOMER NAME:	MROWP052577

DETAILED EQUIPMENT LAYOUT

SHEET NUMBER:

C-102







### NOTES

- BASED ON APPROVED ATC
  APPLICATION 13619927, DATED
  N/A. CONFIRM WITH AT&T
  MOBILITY REP FOR APPLICABLE
  UPDATES/REVISIONS AND MOST
  RECENT RFDS FOR NSN
  CONFIGURATION (CONFIG). GC TO
  CAP ALL UNUSED PORTS.
- CONFIRM SPACING OF PROPOSED EQUIP DOES NOT CAUSE TOWER CONFLICTS NOR IMPEDE TOWER CLIMBING PEGS.
- THE ANTENNA ORIENTATION PLAN IS A SCHEMATIC. ATC DID NOT CONFIRM EXISTING SITE CONDITIONS INCLUDING, BUT NOT LIMITED TO, ANTENNA AZIMUTHS, MOUNT CONFIGURATIONS AND TOWER ORIENTATION. SCALES SHOWN ARE FOR REFERENCE ONLY AND EXISTING DIMENSIONS ARE APPROXIMATE. THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO INSTALLATION AND NOTIFY ATC OF ANY DISCREPANCIES.
- 4. CONTRACTOR TO ENSURE PROPER SEPARATION IN ACCORDANCE WITH AT&T'S FIRSTNET REQUIREMENTS (SEE SHEET R-607)

1 CURRENT ANTENNA PLAN

			1		NNA SCHEDULE											
LOCATION		ANTENNA SUMMARY			NON ANTENNA SUMMARY											
SECTOR	RAD	AZ	POS	ANTENNA	BAND	STATU S	ADDITIONAL TOWER MOUNTED EQUIPMENT	STATUS								
							_	RMN								
			A1	COMMSCOPE NNH4-65C-R6	LTE 700/LTE PCS/5G PCS/LTE AWS/5G AWS	RMN	AIRSCALE RRH 4T4R B12/14 320W AHLBA	RMN								
ALPHA	153'	10°			AW3/30 AW3		AIRSCALE RRH 4T4R B25/66 320W AHFIB	RMN								
ALFNA	155	10	A2	ANDREW SBNHH-1D65C	LTE WCS	RMN	RRH4X25-WCS-4R	RMN								
			А3	COMMSCOPE SBJAH4-1D65C-DL	UMTS 850	RMV	-	RMN								
			A4	COMMSCOPE NNH4-65C-R6	5G 850	RMN	AIRSCALE RRH 4T4R B5 160W AHCA	RMN								
					-	RMN										
			B1	COMMSCOPE NNH4-65C-R6	LTE 700/LTE PCS/5G PCS/LTE AWS/5G AWS	RMN	AIRSCALE RRH 4T4R B12/14 320W AHLBA	RMN								
		120°			711107 00 71110		AIRSCALE RRH 4T4R B25/66 320W AHFIB	RMN								
BETA	153'		120°	120°	B2	ANDREW SBNHH-1D65C	LTE WCS	RMN	RRH4X25-WCS-4R	RMN						
			В3	COMMSCOPE SBJAH4-1D65C-DL	UMTS 850	RMV	-	RMN								
											B4	COMMSCOPE NNH4-65C-R6	5G 850	RMN	AIRSCALE RRH 4T4R B5 160W AHCA	RMN
					(		-	RMN								
			C1	NNHA-65C-R6 PCS/5	LTE 700/LTE PCS/5G PCS/LTE AWS/5G AWS	RMN	AIRSCALE RRH 4T4R B12/14 320W AHLBA	RMN								
					AW3/ 36 AW3		AIRSCALE RRH 4T4R B25/66 320W AHFIB	RMN								
GAMMA	153'	230°	C2	ANDREW SBNHH-1D65C	LTE WCS	RMN	RRH4X25-WCS-4R	RMN								
			С3	COMMSCOPE SBJAH4-1D65C-DL	UMTS 850	RMV	-	RMN								
			C4	COMMSCOPE NNH4-65C-R6	5G 850	RMN	AIRSCALE RRH 4T4R B5 160W AHCA	RMN								

EXISTING AND FINAL

CONFIGURATIONS ARE BASED

VERIFY EXISTING CONDITIONS.

ON RFDS. CONTRACTOR TO

EXISTING FIBER DISTRIBUTION/C	VP BOX	EXISTING CABLING SUMMARY				
MODEL NUMBER	STATUS	COAX	HYBRID	STATUS		
(3) DC6-48-60-18-8F	RMN	(12) 1–5/8"	(1) 18 PAIR FIBER TRUNK	RMN		
_	-	-	(1) 12 PAIR FIBER TRUNK	RMN		
_	-	-	(4) #6 AWG DC CABLES	RMN		
_	-	-	(2) #8 AWG DC CABLES	RMV		

### CABLE LENGTHS FOR JUMPERS

SQUID TO RRU: 15' RRU TO ANTENNA: 10'

STATUS ABBREVIATIONS
RMY: TO BE REMOVED
RMN: TO REMAIN
REL: TO BE RELOCATED
ADD: TO BE ADDED

EQUIPMENT SCHEDULES





49030 Pontiac Trail, Suite 400 Wixom, Michigan 48393 PHONE: (248) 705-9212

l	REV.	DESCRIPTION	BY	DATE
l	A.	PRELIM	RC	04/09/21
l	$\triangle$	FINAL CD	RC	06/25/21
l	$\overline{\wedge}$			
l				

ATC SITE NUMBER:

307538


ATC SITE NAME:

DUBLIN OH

AT&T MOBILITY SITE NAME:

DUBLIN

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN, OH 43017



NAME: PETER LICHOMSKI LICENSE NO: 14/6266 EXP DATE: 12/31/2021



DATE DRAWN: 04/06/21

ATC JOB NO: 13619927

CUSTOMER ID: OHL03059

CUSTOMER NAME: MROWP052577

CURRENT ANTENNA
PLAN AND EXISTING
ANTENNA SCHEDULE

SHEET NUMBER:

C-401

PER MOUNT ANALYSIS COMPLETED BY POD, DATED 06/02/2021, THE EXISTING MOUNT CAN ADEQUATELY SUPPORT THE PROPOSED LOADING

PROPOSED RRUS MUST BE

FROM FIRSTNET ANTENNAS

EXISTING AND FINAL CONFIGURATIONS ARE BASED ON RFDS. CONTRACTOR TO

VERIFY EXISTING CONDITIONS.

INSTALLED A MINIMUM OF 8" AWAY

EXISTING ANDREW SBNHH-1D65C ANTENNA (TO REMAIN) (TYP.3) EXISTING COMMSCOPE NNH4-65C-R6 ANTENNA EXISTING ALCATEL-LUCENT (TO REMAIN) (TYP.6) RRH4x25-WCS-4R RRU (TO REMAIN) EXISTING NOKIA AIRSCALE RRH 4T4R B5 160W AHCA (TO REMAIN) (TYP.3) EXISTING AIRSCALE DUAL RRH 4T4R -B12/14 320W AHLBA RRU (TO EXISTING AIRSCALE DUAL RRH REMAIN) (TYP.3) 4T4R B25/66 320W AHFIB RRU (TO REMAIN) (TYP.3) EXISTING DC6-48-60-18-8F SQUID (TO REMAIN) (TYP.3) PROPOSED NOKIA AEQK ANTENNA (1 PER SECTOR) (TYP.3)





- BASED ON APPROVED ATC
  APPLICATION 13619927, DATED
  N/A. CONFIRM WITH AT&T
  MOBILITY REP FOR APPLICABLE
  UPDATES/REVISIONS AND MOST
  RECENT RFDS FOR NSN
  CONFIGURATION (CONFIG). GC TO
  CAP ALL UNUSED PORTS.
  CONFIRM SPACING OF PROPOSED
- CONFIRM SPACING OF PROPOSED EQUIP DOES NOT CAUSE TOWER CONFLICTS NOR IMPEDE TOWER CLIMBING PEGS.
- CLIMBING PEGS.
  THE ANTENNA ORIENTATION PLAN
  IS A SCHEMATIC. ATC DID NOT
  CONFIRM EXISTING SITE
  CONDITIONS INCLUDING, BUT NOT
  LIMITED TO, ANTENNA AZIMUTHS,
  MOUNT CONFIGURATIONS AND
  TOWER ORIENTATION. SCALES
  SHOWN ARE FOR REFERENCE
  ONLY AND EXISTING DIMENSIONS
  ARE APPROXIMATE. THE
  CONTRACTOR SHALL VERIFY ALL
  EXISTING CONDITIONS PRIOR TO
  INSTALLATION AND NOTIFY ATC
  OF ANY DISCREPANCIES
- OF ANY DISCREPANCIES.

  4. CONTRACTOR TO ENSURE PROPER SEPARATION IN ACCORDANCE WITH AT&T'S FIRSTNET REQUIREMENTS (SEE SHEET R-607)

FINAL ANTENNA PLAN

				FINAL ANTENI	NA SCHEDULE						
ı	LOCATION			ANTENNA SUM	IMARY		NON ANTENNA SUMMA	RY			
SECTOR RAD AZ		AZ	POS ANTENNA		BAND STATU		ADDITIONAL TOWER MOUNTED EQUIPMENT	STATUS			
					LTE 700/LTE		_	RMN			
			A1	COMMSCOPE NNH4-65C-R6	PCS/5G PCS/LTE AWS/5G AWS	RMN	AIRSCALE RRH 4T4R B12/14 320W AHLBA	RMN			
ALPHA	1.5.3'	10°			, 0, 00 , 0		AIRSCALE RRH 4T4R B25/66 320W AHFIB	RMN			
ALFTIA	155		A2	ANDREW SBNHH-1D65C	LTE WCS	RMN	RRH4X25-WCS-4R	RMN			
			A3	NOKIA AEQK	5G	ADD	-	RMN			
			A4	COMMSCOPE NNH4-65C-R6	5G 850	RMN	AIRSCALE RRH 4T4R B5 160W AHCA	RMN			
							_	RMN			
			B1	COMMSCOPE NNH4-65C-R6	LTE 700/LTE PCS/5G PCS/LTE AWS/5G AWS	RMN	AIRSCALE RRH 4T4R B12/14 320W AHLBA	RMN			
					AWS/ 30 AWS		AIRSCALE RRH 4T4R B25/66 320W AHFIB	RMN			
BETA	153'	120°	B2	ANDREW SBNHH-1D65C	LTE WCS	RMN	RRH4X25-WCS-4R	RMN			
			В3	NOKIA AEQK	5G	ADD	-	RMN			
		E	B4	COMMSCOPE NNH4-65C-R6	5G 850	RMN	AIRSCALE RRH 4T4R B5 160W AHCA	RMN			
					(		-	RMN			
			C1	COMMSCOPE NNH4-65C-R6	C1 COMMSCOPE PC	C1 COMMSCOPE PCS/5G P	LTE 700/LTE PCS/5G PCS/LTE AWS/5G AWS	RMN	. RMN	AIRSCALE RRH 4T4R B12/14 320W AHLBA	RMN
					AND/ JU AND		AIRSCALE RRH 4T4R B25/66 320W AHFIB	RMN			
GAMMA	153'	230°	C2	ANDREW SBNHH-1D65C	LTE WCS	RMN	RRH4X25-WCS-4R	RMN			
			C3	NOKIA AEQK	5G	ADD	-	RMN			
			C4	COMMSCOPE NNH4-65C-R6	5G 850	RMN	AIRSCALE RRH 4T4R B5 160W AHCA	RMN			

FINAL FIBER DISTRIBUTION/C	VP BOX	FINAL CABLING SUMMARY			
MODEL NUMBER	STATUS	COAX	HYBRID	STATUS	
(3) DC6-48-60-18-8F	RMN (12) 1-5/8"		-5/8" (1) 18 PAIR FIBER TRUNK & (1) 12 PAIR FIBER TRUNK		
-	-	_	(4) #6 AWG DC CABLES	RMN	
_	-	_	(2) #6 AWG DC CABLES	ADD	

CABLE LENGTHS FOR JUMPERS

SQUID TO RRU: 15' RRU TO ANTENNA: 10'

STATUS ABBREVIATIONS
RMV: TO BE REMOVED
RMN: TO REMAIN
REL: TO BE RELOCATED

ADD: TO BE ADDED

EQUIPMENT SCHEDULES





49030 Pontiac Trail, Suite 400 Wixom, Michigan 48393 PHONE: (248) 705-9212

REV.	DESCRIPTION	BY	DATE
<u> </u>	PRELIM	RC_	04/09/21
△	FINAL CD	RC	06/25/21
$\triangle$			
$\overline{\wedge}$			
$\overline{\wedge}$			

ATC SITE NUMBER:

307538


ATC SITE NAME:

DUBLIN OH

AT&T MOBILITY SITE NAME:

DUBLIN

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN. OH 43017



NAME: PETER LICHOMGKI LICENGE NO: IAI6146 EXP DATE: |2/3|/202|




PROPOSED ANTENNA
PLAN AND FINAL

\_\_\_\_

SHEET NUMBER:

ANTENNA SCHEDULE

0



ANTENNA DETAIL
SCALE: N.T.S





49030 Pontiac Trail, Suite 400 Wixom, Michigan 48393 PHONE: (248) 705-9212

REV.	DESCRIPTION	BY	DATE
A.	PRELIM	RC	04/09/21
$\triangle$	FINAL CD	RC	06/25/21
$\overline{\wedge}$			
$\overline{\wedge}$			

ATC SITE NUMBER:

307538

ATC SITE NAME:

### **DUBLIN OH**

AT&T MOBILITY SITE NAME:

### DUBLIN

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN, OH 43017

SEAL:



NAME: PETER LICHOMSKI LICENSE NO: |4|6166 EXP DATE: |2/3|/202|



	DATE DRAWN:	04/06/21
	ATC JOB NO:	13619927
	CUSTOMER ID:	OHL03059
Ш	CUSTOMER NAME:	MROWP052577


## CONSTRUCTION DETAILS

SHEET NUMBER:

REVISION:


C-501

0



- THIS DETAIL IS INTENDED TO SHOW THE GENERAL GROUNDING REQUIREMENTS. SLIGHT ADJUSTMENTS MAY BE REQUIRED BASED ON EXISTING SITE CONDITIONS. THE CONTRACTOR SHALL MAKE FIELD ADJUSTMENTS AS NEEDED AND INFORM THE CONSTRUCTION MANAGER OF ANY CONFLICTS.
- SITE GROUNDING SHALL COMPLY WITH AT&T MOBILITY GROUNDING STANDARDS, LATEST EDITION, AND COMPLY WITH AT&T MOBILITY GROUNDING CHECKLIST, LATEST VERSION. WHEN NATIONAL AND LOCAL GROUNDING CODES ARE MORE STRINGENT THEY SHALL






### **GROUND BAR NOTES**

- GROUND KITS COME WITH ALL HARDWARE, NUTS, BOLTS, WASHERS, ETC. EXCEPT THE STRUCTURAL MOUNTING MEMBER(S).
- 2. GROUND BAR SHALL BE BOLTED TO STRUCTURAL MEMBER OR ANCHORED TO CONCRETE SLAB W/ HILTI KWIK BOLT III.







- GROUND KIT NOTES:

  1. DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.
- 2. CONTRACTOR SHALL PROVIDE WEATHERPROOFING KIT (ANDREW PART NUMBER 221213) AND INSTALL/TAPE PER MANUFACTURER'S SPECIFICATIONS.

## CABLE GROUND KIT CONNECTION DETAIL






### **GROUND BAR NOTES:**

- GROUND BAR KITS COME WITH ALL HARDWARE, NUTS, BOLTS, WASHERS, ETC. EXCEPT THE STRUCTURAL MOUNTING MEMBER(S).
- 2. GROUND BAR TO BE BONDED DIRECTLY TO TOWER.

## **TOWER GROUND BAR DETAIL**









49030 Pontiac Trail. Suite 40 Wixom, Michigan 48393 PHONE: (248) 705-9212

I	REV	. DESCRIPTION	BY	DATE
I	A	PRELIM	RC	04/09/21
I	$\triangle$	FINAL CD	RC	06/25/21
I	$\wedge$			
I	$\overline{\wedge}$			
I	$\overline{\wedge}$			

ATC SITE NUMBER:

307538


ATC SITE NAME:

**DUBLIN OH** 

AT&T MOBILITY SITE NAME:

**DUBLIN** 

SITE ADDRESS: 5780 SHIER-RINGS ROAD DUBLIN, OH 43017



NAME: PETER LICHOMSKI LICENSE NO: |4|6266 EXP DATE: |2/3|/202|



DATE DRAWN: 04/06/21 ATC JOB NO: 13619927 CUSTOMER ID: OHL03059 CUSTOMER NAME: MROWP052577


> **GROUNDING DETAILS**

SHEET NUMBER:

E-501

REVISION

MAIN GROUND BAR DETAIL



ANTENNA SPECIFICATIONS				
ANTENNA MODEL	Α	В	С	WEIGHT (LBS)
AEQK	29.5"	17.2"	9.5"	99.2

SUPPLEMENTAL

SHEET NUMBER:


REVISION:


R-601


1

EQUIPMENT MANUFACTURER DETAIL - FOR REFERENCE ONLY

SCALE: NOT TO SCALE









This report was prepared for American Tower Corporation by



### **Antenna Mount Analysis Report**

ATC Site Name : Dublin OH

ATC Site Number : 307538

Engineering Number : 13619927\_C8\_01

Mount Elevation : 152.5 ft

Carrier : AT&T MOBILITY

Carrier Site Name : MROWP052577

Carrier Site Number : OHL03059

Site Location : 5580 Shier Rings Rd

**Dublin, OH 43016** 

40.097000,-83.140200

County : Franklin

Date : June 2, 2021

Max Usage : 88%

Result : Pass

Prepared By: Dario Pelemis Matthew A. Houdeshell Project Manager

MATTHEW A. HOUDESHELL PE.79012

6/2/21

POD GROUP - 1033 E. Turkeyfoot Lake Road, Suite 206 - Akron, OH 44312 - 330-961-7432 - www.podgrp.com



Eng. Number 13619927\_C8\_01 June 2, 2021 Page 1

### Introduction

The purpose of this report is to summarize results of the antenna mount analysis performed for T-Mobile at 153 ft

### **Supporting Documents**

Spec. Sheet	Sheet Spec Sheet for SitePro1 RMQP-496-HK	
Structural Analysis ATC Engineering #OAA749908_C3_01, dated July 25, 2019		
RFDS	RFDS dated March 20, 2021	
Photos	Site photos from 2020	

### **Analysis**

This antenna mount was analyzed using RISA-3D v17 analysis software

Basic Wind Speed:	108 mph, Vult (3-Second Gust)	
Basic Wind Speed w/ Ice:	40 mph (3-Second Gust) w/ 1" Radial Ice (Escalating)	
Codes:	TIA-222-H	
Structure Class:	II	
Exposure Category:	В	
Topographic Factor Procedure:	Method	
Topographic Feature:	Flat	
Crest Height:	Oft	
Spectral Response:	Ss = .122, S <sub>1</sub> = .06	
Site Class:	D (assumed)	
Live Loads:	Lm = 500 lbs, Lv = 250 lbs	

### Conclusion

Based on the analysis results, the antenna mount meets the requirements per the applicable codes listed above. The mount can support the equipment as described in this report.

If you have any questions or require additional information, please contact POD Group via email at mhoudeshell@podgrp.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

POD GROUP - 1033 E. Turkeyfoot Lake Road, Suite 206 - Akron, OH 44312 - 330-961-7432 - www.podgrp.com

SUPPLEMENTAL



Eng. Number 13619927\_C8\_01 June 2, 2021 Page 2

### **Antenna Loading**


Mount Centerline (ft)	Antenna Centerline (ft)	Qty	Antenna Model
		3	Nokia AEQK AirScale MAA 64T64R 192AE n77 200W
		3	Commscope SBNHH-1D65C (66.1lb)
		6	Commscope NNH4-65C-R6 (102.1 lbs)
152.5	152.5 153.0	3	Raycap DC6-48-60-18-8F ("Squid")*
		3	Nokia AirScale Dual RRH 4T4R B12/14 320W AHLBA w/ cover
		3	Nokia AirScale RRH 4T4R B5 160W AHCA
		3	Alcatel-Lucent RRH4x25-WCS (91lb)
		3	AirScale Dual RRH 4T4R B25/66 320W AHFIB (66.1lbs)

<sup>\*</sup>Equipment assumed to be mounted directly to tower.

### Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Plates	88%	Pass
Mount Pipes	57%	Pass
Rails	50%	Pass
Angles	41%	Pass
Faces	18%	Pass
Standoffs	17%	Pass
Supports	16%	Pass
Kickers	14%	Pass


POD GROUP - 1033 E. Turkeyfoot Lake Road, Suite 206 - Akron, OH 44312 - 330-961-7432 - www.podgrp.com



SUPPLEMENTAL

# RF REQUIREMENTS FOR 700 B14 FIRSTNET, 700 B12, 700D B29 ANTENNA SEPARATION

- ☐ Horizontal separation (side to side of antenna): >= 3'
- ☐ Vertical separation (between the tips of the antennas): > 3'
- $\square$  Inter-sector separation: > 3' between the center of the antenna backplanes.



- ☐ Please note additional horizontal separation may be required if B14 antennas azimuth are different from others or antennas are severely angled with respect to the mount.
- ☐ Typical 3' horizontal separation can tolerate skew angle up to 6°.



**SUPPLEMENTAL**